TOWNSHIP of HOPEWELL
MERCER COUNTY

201 WASHINGTON CROSSING – PENNINGTON ROAD
TITUSVILLE, NEW JERSEY 08560-1410

PROJECT / APPLICATION

BLOCK: 93

LOT: 19, 20, 45.01, 46, p/o 60

ADDRESS: 61 NURSERY RD., SCOTCH RD., NURSERY RD., NURSERY RD., 137 NURSERY RD.

PROJECT NAME: MAJOR SUBDIVISION, PRELIMINARY/FINAL AND SITE PLAN, PRELIMINARY/FINAL (VENUE AT HOPEWELL)

SOIL EROSION CONTROL & STEEP SLOPE PLAN 4.2.25

PageSetUp: ---- PlotStyleTable: BCG-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:31:31AM, dino.spinelli, LAYOUT: SHT-16A

XREFs: 081391_PGRD.dwg
081073.01 Deer Valley-Hopewell-sheets 2-13.dwg
081391_PBASE.dwg
Deer Valley Easement.dwg

NURSERY ROAD
(TO BE DEDICATED AS PUBLIC STREET)
(VARIABLE WIDTH R.O.W.)

SCOTCH ROAD
(VARIABLE WIDTH R.O.W.)

ROAD B
(TO BE DEDICATED AS PUBLIC STREET)

PROPOSED R.O.W.

PROPOSED RIGHT-OF-WAY

LIMIT OF DISTURBANCE (TYP.)

SILT FENCE /(TYP.)

INLET PROTECTION (TYP.)

SAWCUT

SEE SHEET B
SEE SHEET A

N86° 24' 08"E - 1002.69'

S03° 35' 52"E - 252.60'

L=109.23'
R=5,689.65'
Δ=1°06'00"
(DEED)

S03°46'51"E 78.06' (DEED)

S03°46'51"E 178.26' (DEED)

N87°30'00"W 178.26' (DEED)

S03°46'51"E 178.26' (DEED)

S50°00'00"W 357.42' (DEED)

N87°30'00"W 1275.26' (DEED)

SCALE: 1"=30'
0
30
60
120 ft.

6			
5			
4	REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
3	REVISED PER ENGINEERING REVIEW	2/14/25	SAD
2	REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
1	REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD
	REVISION	DATE	CHKD

12			
11			
10			
9			
8			
7			
	REVISION	DATE	CHKD

SHEET No. 16A OF

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL
SOIL EROSION AND SEDIMENT CONTROL PLAN
BLOCK 93, LOTS 19, 20, 45.01, 46 & 60
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

Bowman Consulting Group Ltd
3 Paragon Way, Suite 170
Freehold, New Jersey 07728
bowman.com
E-mail: NJ@Bowman.com
Phone: 732-665-5500
FAX: 732-665-5501
NJ Certificate of Authorization No. 24GA2822600

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

Bowman

PROJ.: 081391-01-001
DATE: 06/25/2024
CHKD: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY TO WHOM IT IS ISSUED AND CONTRACTED ON TO WHOM IT IS CERTIFIED. THIS DRAWING MAY NOT BE COPIED, REUSED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP, LTD.
© 2025 BOWMAN CONSULTING GROUP, LTD.
ALL RIGHTS RESERVED

PageSetUp: ---- PlotStyleTable: BCG-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:34:08AM, dino.spinelli, LAYOUT: SHT-16B

XREFS: 081391_PGRD.dwg
081073.01 Deer Valley-Hopewell-sheets 2-13.dwg
081391_PBASE.dwg
Deer Valley Easement.dwg

ROAD B
(TO BE DEDICATED AS PUBLIC STREET)
(50' R.O.W.)

ROAD C
(TO BE DEDICATED AS PUBLIC STREET)
(50' R.O.W.)

SEE SHEET B
SEE SHEET A

LIMIT OF DISTURBANCE (TYP.)

INLET PROTECTION (TYP.)

SILT FENCE (TYP.)

S87°12'00"W 1212.00' (DEED)

S6°00'01"E 417.41' (DEED)

N2°12'50"E 412.01' (DEED)

S02° 13' 25"E - 517.74'

N84° 24' 05"E - 294.90'

N85° 26' 18"E - 929.55'

PROPOSED INLET PROTECTION

PROPOSED SILT FENCE

PROPOSED LIMIT OF DISTURBANCE

PROPOSED TREE PROTECTION FENCE

PROPOSED SILT FENCE OUTLET

PROPOSED STABILIZED CONSTRUCTION ENTRANCE

PROPOSED CONCRETE WASHOUT

PROPOSED STOCKPILE

PROPOSED SEDIMENT BASIN

PROPOSED SEDIMENT BASIN OUTLET

PROPOSED TEMPORARY SWALE

PROPOSED TEMPORARY SWALE OUTLET

PROPOSED TEMPORARY SEDIMENT TRAP

PROPOSED TEMPORARY SEDIMENT TRAP OUTLET

PROPOSED DIVERSION SWALE

PROPOSED DIVERSION SWALE OUTLET

PROPOSED TEMPORARY DIVERSION

PROPOSED TEMPORARY DIVERSION OUTLET

PROPOSED TEMPORARY SEDIMENT TRAP

PROPOSED TEMPORARY SEDIMENT TRAP

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL
SOIL EROSION AND SEDIMENT CONTROL PLAN
BLOCK 93, LOTS 19, 20, 45.01, 46 & 60
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

SHEET No. 16C OF

Bowman Consulting Group Ltd
3 Paragon Way, Suite 120
Freehold, New Jersey 07728
Phone: 732-665-6500
FAX: 732-665-6501
NJ Certificate of Authorization No. 24GA28222600
E-mail: NJ@bowman.com

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

Bowman

REVISION	DATE	CHK'D
1 REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD
2 REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
3 REVISED PER ENGINEERING REVIEW	2/14/25	SAD
4 REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
5		
6		
7		
8		
9		
10		
11		
12		

PROJ. 081391-01-001
DATE: 06/25/2024
CHK'D: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THIS DRAWING MAY NOT BE COPIED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP LTD.
© 2025 BOWMAN CONSULTING GROUP LTD
ALL RIGHTS RESERVED

LIMIT OF DISTURBANCE (TYP.)

SILT FENCE /(TYP.)

INLET PROTECTION (TYP.)

ROAD A (TO BE DEDICATED AS PUBLIC STREET) (60' R.O.W.)

ROAD B (TO BE DEDICATED AS PUBLIC STREET) (60' R.O.W.)

ROAD C (TO BE DEDICATED AS PUBLIC STREET) (60' R.O.W.)

ROAD 12 (TO BE DEDICATED AS PUBLIC STREET) (60' R.O.W.)

PROPOSED RIGHT-OF-WAY

SEE SHEET C

SEE SHEET D

SEE SHEET E

SEE SHEET F

LOT 20 BLOCK 93 (DB.3907, P6136)

SCALE 1"=50'

XREFS: 081391_TGRD.dwg
081077.01 Deer Valley-Hopewell-sheets 2-13.dwg
081391_PBASE.dwg
Deer Valley Easement.dwg

PageSetup:---- PlotStyleTable: BCG-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:35:21AM, dmcspinelli, LAYOUT:SHT-16C

PageSetUp: ----- PlotStyleTable: BCG-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:37:49AM, dino.spinelli, LAYOUT:SHT-16D
XREFs: 081391_PSHD.dwg
081391_Deer Valley-Hopewell-sheets 2-13.dwg
081071_PBASE.dwg
081391_Deer Valley Easement.dwg

SEE SHEET G
SEE SHEET D

TEMPORARY CONSTRUCTION FENCE (TYP.)

TEMPORARY CONSTRUCTION FENCE (TYP.)

SILT FENCE (TYP.)

LIMIT OF DISTURBANCE (TYP.)

ROAD 12

ROAD G

INLET PROTECTION (TYP.)

PROPOSED RIGHT-OF-WAY

BLOCK 93 LOT 20 (DB. 3907, PG 136)

SEE SHEET D
SEE SHEET P

SEE SHEET A
SEE SHEET E

N/F BLOCK 93 LOT 21

N/F BLOCK 93 LOT 19

N/F BLOCK 93 LOT 22

N/F BLOCK 93 LOT 23

N/F BLOCK 93 LOT 24

N/F BLOCK 93 LOT 25

N/F BLOCK 93 LOT 26

N/F BLOCK 93 LOT 27

N/F BLOCK 93 LOT 28

N/F BLOCK 93 LOT 29

N/F BLOCK 93 LOT

XREFs: (08139)-Grading.dwg (08139)-Plan Set Key.dwg (08139)-Site Plan.dwg Deer Valley Easement.dwg

TEMPORARY CONSTRUCTION FENCE (TYP.)

SILT FENCE /(TYP.)

LIMIT OF DISTURBANCE (TYP.)

INLET PROTECTION (TYP.)

TEMP. STOCKPILE LOCATION (TYP.)

ROAD A
(TO BE DEDICATED AS PUBLIC STREET)
(60' R.O.W.)

ROAD B
(TO BE DEDICATED AS PUBLIC STREET)
(50' R.O.W.)

ROAD C
(TO BE DEDICATED AS PUBLIC STREET)
(50' R.O.W.)

SEE SHEET E

SEE SHEET F

S89°31'00"W 1,212.00' (DEED)

NO.	REVISION	DATE	DRWN
12			
11			
10			
9			
8			
7			
6			
5			
4	REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
3	REVISED PER ENGINEERING REVIEW	2/14/25	SAD
2	REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
1	REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD

PROJ. 08139-01-001
DSGN. SAD/DRM/DAH
CHKD. SAD

© COPYRIGHT 2024 BOWMAN CONSULTING GROUP, LTD.
THIS DRAWING AND ALL INFORMATION, DESIGNS, CONCEPTS, AND IDEAS CONTAINED THEREIN ARE THE PROPERTY OF BOWMAN AND THE WORK WAS CONTRACTED ONLY TO THE USE SHOWN. THIS DRAWING SHALL NOT BE COPIED, REUSED, DISCLOSED, LOANED OR ALTERED IN ANY WAY WHATSOEVER WITHOUT THE PRIOR, EXPRESS, WRITTEN CONSENT OF BOWMAN CONSULTING GROUP, LTD. ALL RIGHTS RESERVED.

Bowman

Bowman Consulting Group Ltd
412 Mt. Kemble Avenue
Suite 110C
Morristown, New Jersey 07960
Phone: 732-665-5500
FAX: 732-665-5551
NJ Certificate of Authorization
No. 24GA28222600

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR

VENUE AT HOPEWELL

SOIL EROSION AND SEDIMENT CONTROL PLAN

BLOCK 58.01, LOTS 29 & 34.01 | 464 Rt. 31

TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

SHEET No.
16E
OF

SCALE 1" = 30'

PageSetUp: ----- PlotStyleTable: BCG-NJ.ctb
X:\08139 - Nursery Road-Hopewell\08139-01-001 (ENG) - Venue at Hopewell 3P\Engineering\Engineering Plans\02 Site Plans\(08139)-SP-SESC.dwg 04/01/25 11:39:27AM dina.spinelli LAYOUT:3HT-16E

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL
SOIL EROSION AND SEDIMENT CONTROL PLAN
BLOCK 93, LOTS 19, 20, 45.01, 46 & 60
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

SHEET No. 16F OF

Bowman Consulting Group Ltd
3 Paragon Way, Suite 120
Freehold, New Jersey 07728
Phone: 732-665-6500
FAX: 732-665-6501
NJ Certificate of Authorization No. 24GA28222600
e-mail: NJ@bowman.com

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

Bowman

REVISION	DATE	CHK'D
1 REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD
2 REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
3 REVISED PER ENGINEERING REVIEW	2/14/25	SAD
4 REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
5		
6		
7		
8		
9		
10		
11		
12		

REVISION	DATE	CHK'D

PROJ. 081391-01-001
DATE: 06/25/2024
CHK'D: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. ANY REUSE WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP LTD. UPON FOR ANY OTHER PURPOSE SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO BOWMAN CONSULTING GROUP LTD.
© 2025 BOWMAN CONSULTING GROUP LTD
ALL RIGHTS RESERVED

XREFS: 081391_FGRD.dwg
081077-01 Deer Valley-Hopewell-sheets 2-13.dwg
081391_PBASE.dwg
Deer Valley Easement.dwg

Pagestitle: ---- PlotStyleTable: BCG-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:40:29AM, dlno.splmlll, LAYOUT:SHT-16F

PageSetUp: ---- PlotStyleTable: BCG-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:41:35AM, dino.spinelli, LAYOUT: SHT-16G

XREFs: 081391_PSKD.dwg
081071_Deer Valley-Hopewell-sheets 2-13.dwg
081391_PBASE.dwg
Deer Valley Easement.dwg

SEE SHEET F
SEE SHEET G
SEE SHEET D

ROAD E
(TO BE DEDICATED AS PUBLIC STREET)
50' R.O.W.

ROAD F
(TO BE DEDICATED AS PUBLIC STREET)
50' R.O.W.

ROAD 10
(TO BE DEDICATED AS PUBLIC STREET)
50' R.O.W.

INLET PROTECTION (TYP.)

TEMP. STOCKPILE LOCATION (TYP.)

PROPOSED RIGHT-OF-WAY

LIMIT OF DISTURBANCE (TYP.)

SILT FENCE (TYP.)

TEMPORARY CONSTRUCTION FENCE (TYP.)

S04° 51' 22"E - 300.00'

S41° 52' E - 206.5

S2°W 216.82'

N2°44'41"W 2.29' (DEED)

N5°02'21"W 375.06' (DEED)

N5°02'21"W 65.72' (DEED)

S87°57'39"W 100.00' (DEED)

S87°57'39"W 111.59' (DEED)

N87°57'39"E 28.46' (DEED)

N87°57'39"E 69.58' (DEED)

S87°57'39"W 43.61' (DEED)

S87°57'39"W 48.87' (DEED)

N87°57'39"E 69.58' (DEED)

S87°57'39"W 19.58' (DEED)

N87°57'39"E 60.01' (DEED)

N75°14'52"W 14.99' (DEED)

S87°57'39"W 100.00' (DEED)

S0°22'05"W 120.04' (EASEMENT)

S0°22'05"W 141.96' (EASEMENT)

N0°22'05"E 206.72' (EASEMENT)

S87°57'39"W 269.58' (EASEMENT)

N87°57'39"E 269.58' (EASEMENT)

L=90.00'
R=60.00'
(EASEMENT)

L=94.25'
R=60.00'
(EASEMENT)

L=141.42'
R=90.00'
(EASEMENT)

L=141.42'
R=90.00'
(EASEMENT)

SCALE: 1"=30'

0 30 60 120 ft.

SHEET No.	OF
16G	

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL
SOIL EROSION AND SEDIMENT CONTROL PLAN
BLOCK 93, LOTS 19, 20, 45.01, 46 & 60
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

Bowman Consulting Group Ltd
3 Paragon Way, Suite 170
Freehold, New Jersey 07728
bowman.com
E-mail: NJ@Bowman.com
Phone: 732-665-5500
FAX: 732-665-5501
NJ Certificate of Authorization No. 24GA28222600

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

Bowman

PROJ.: 081391-01-001
DATE: 06/25/2024
CHKD: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY TO WHOM IT IS ISSUED AND TO CONTRACTORS ON THE WORK IT IS CERTIFIED. THIS DRAWING MAY NOT BE COPIED, REUSED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP, LTD.
© 2025 BOWMAN CONSULTING GROUP, LTD.
ALL RIGHTS RESERVED

	REVISION	DATE	CHKD
6			
5			
4	REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
3	REVISED PER ENGINEERING REVIEW	2/14/25	SAD
2	REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
1	REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD

	REVISION	DATE	CHKD
12			
11			
10			
9			
8			
7			

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL
SOIL EROSION AND SEDIMENT
CONTROL PLAN
BLOCK 33, LOTS 19, 20, 45.01, 48 & 60
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

SHEET No. 16H OF

Bowman Consulting Group Ltd
3 Paragon Way Suite 120
Freehold, New Jersey 07728
Phone: 732-665-6500
FAX: 732-665-6501
NJ Certificate of Authorization No. 24GA28222600
E-mail: NJ@bowman.com

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

Bowman

REVISION	DATE	CHK'D
1 REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD
2 REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
3 REVISED PER ENGINEERING REVIEW	2/14/25	SAD
4 REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
5		
6		
7		
8		
9		
10		
11		
12		

REVISION	DATE	CHK'D

PROJ. 081391-01-001
DATE: 06/25/2024
CHK'D: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THIS DRAWING SHALL NOT BE LOANED, COPIED OR REPRODUCED IN ANY FORM OR BY ANY MEANS, WHETHER ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP, LTD. UPON FOR ANY OTHER PURPOSE.
© 2025 BOWMAN CONSULTING GROUP, LTD.
ALL RIGHTS RESERVED

XREFS: 081391_FGRD.dwg
081077.01 Deer Valley-Hopewell-sheets 2-13.dwg
081391_PBASE.dwg
Deer Valley Easement.dwg

PageSetup:---- PlotStyleTable: BCC-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:43:10AM, dno.spinelli, LAYOUT:SHT-16H

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL
SOIL EROSION AND SEDIMENT
CONTROL PLAN
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY
BLOCK 93, LOTS 19, 20, 45.01, 46 & 60

SHEET No. 16I OF

Bowman Consulting Group Ltd
3 Paragon Way, Suite 120
Freehold, New Jersey 07728
Phone: 732-665-6500
FAX: 732-665-6501
NJ Certificate of Authorization No. 24GA28222600
E-mail: NJ@bowman.com

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

Bowman

REVISION	DATE	CHK'D
1 REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD
2 REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
3 REVISED PER ENGINEERING REVIEW	2/14/25	SAD
4 REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
5		
6		
7		
8		
9		
10		
11		
12		

PROJ.: 081391-01-001
DATE: 06/25/2024
CHK'D: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. ANY USE OR REUSE OF THIS DRAWING AND/OR THE INFORMATION CONTAINED THEREIN BY ANY OTHER PERSON OR FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP LTD. IS UNLAWFUL AND PROHIBITED.
© 2025 BOWMAN CONSULTING GROUP LTD.
ALL RIGHTS RESERVED

SCALE: 1" = 50'

ROAD 9 (TO BE DEDICATED AS PUBLIC STREET) (50' R.O.W.)

ROAD C (TO BE DEDICATED AS PUBLIC STREET) (50' R.O.W.)

ROAD 6 (TO BE DEDICATED AS PUBLIC STREET) (50' R.O.W.)

TOPSOIL STOCKPILE AREA (TYP.)

TOPSOIL STOCKPILE AREA (TYP.)

SOIL STOCKPILE AREA (TYP.)

SOIL STOCKPILE AREA (TYP.)

SOIL STOCKPILE AREA (TYP.)

SOIL STOCKPILE AREA (TYP.)

SEE SHEET 16J

SEE SHEET 16K

SEE SHEET 16L

SEE SHEET 16M

SEE SHEET 16N

SEE SHEET 16O

SEE SHEET 16P

SEE SHEET 16Q

SEE SHEET 16R

SEE SHEET 16S

SEE SHEET 16T

SEE SHEET 16U

SEE SHEET 16V

SEE SHEET 16W

SEE SHEET 16X

SEE SHEET 16Y

SEE SHEET 16Z

SEE SHEET 16AA

SEE SHEET 16AB

SEE SHEET 16AC

SEE SHEET 16AD

SEE SHEET 16AE

SEE SHEET 16AF

SEE SHEET 16AG

SEE SHEET 16AH

SEE SHEET 16AI

SEE SHEET 16AJ

SEE SHEET 16AK

SEE SHEET 16AL

SEE SHEET 16AM

SEE SHEET 16AN

SEE SHEET 16AO

SEE SHEET 16AP

SEE SHEET 16AQ

SEE SHEET 16AR

SEE SHEET 16AS

SEE SHEET 16AT

SEE SHEET 16AU

SEE SHEET 16AV

SEE SHEET 16AW

SEE SHEET 16AX

SEE SHEET 16AY

SEE SHEET 16AZ

SEE SHEET 16BA

SEE SHEET 16BB

SEE SHEET 16BC

SEE SHEET 16BD

SEE SHEET 16BE

SEE SHEET 16BF

SEE SHEET 16BG

SEE SHEET 16BH

SEE SHEET 16BI

SEE SHEET 16BJ

SEE SHEET 16BK

SEE SHEET 16BL

SEE SHEET 16BM

SEE SHEET 16BN

SEE SHEET 16BO

SEE SHEET 16BP

SEE SHEET 16BQ

SEE SHEET 16BR

SEE SHEET 16BS

SEE SHEET 16BT

SEE SHEET 16BU

SEE SHEET 16BV

SEE SHEET 16BW

SEE SHEET 16BX

SEE SHEET 16BY

SEE SHEET 16BZ

SEE SHEET 16CA

SEE SHEET 16CB

SEE SHEET 16CC

SEE SHEET 16CD

SEE SHEET 16CE

SEE SHEET 16CF

SEE SHEET 16CG

SEE SHEET 16CH

SEE SHEET 16CI

SEE SHEET 16CJ

SEE SHEET 16CK

SEE SHEET 16CL

SEE SHEET 16CM

SEE SHEET 16CN

SEE SHEET 16CO

SEE SHEET 16CP

SEE SHEET 16CQ

SEE SHEET 16CR

SEE SHEET 16CS

SEE SHEET 16CT

SEE SHEET 16CU

SEE SHEET 16CV

SEE SHEET 16CW

SEE SHEET 16CX

SEE SHEET 16CY

SEE SHEET 16CZ

SEE SHEET 16DA

SEE SHEET 16DB

SEE SHEET 16DC

SEE SHEET 16DD

SEE SHEET 16DE

SEE SHEET 16DF

SEE SHEET 16DG

SEE SHEET 16DH

SEE SHEET 16DI

SEE SHEET 16DJ

SEE SHEET 16DK

SEE SHEET 16DL

SEE SHEET 16DM

SEE SHEET 16DN

SEE SHEET 16DO

SEE SHEET 16DP

SEE SHEET 16DQ

SEE SHEET 16DR

SEE SHEET 16DS

SEE SHEET 16DT

SEE SHEET 16DU

SEE SHEET 16DV

SEE SHEET 16DW

SEE SHEET 16DX

SEE SHEET 16DY

SEE SHEET 16DZ

SEE SHEET 16EA

SEE SHEET 16EB

SEE SHEET 16EC

SEE SHEET 16ED

SEE SHEET 16EE

SEE SHEET 16EF

SEE SHEET 16EG

SEE SHEET 16EH

SEE SHEET 16EI

SEE SHEET 16EJ

SEE SHEET 16EK

SEE SHEET 16EL

SEE SHEET 16EM

SEE SHEET 16EN

SEE SHEET 16EO

SEE SHEET 16EP

SEE SHEET 16EQ

SEE SHEET 16ER

SEE SHEET 16ES

SEE SHEET 16ET

SEE SHEET 16EU

SEE SHEET 16EV

SEE SHEET 16EW

SEE SHEET 16EX

SEE SHEET 16EY

SEE SHEET 16EZ

SEE SHEET 16FA

SEE SHEET 16FB

SEE SHEET 16FC

SEE SHEET 16FD

SEE SHEET 16FE

SEE SHEET 16FF

SEE SHEET 16FG

SEE SHEET 16FH

SEE SHEET 16FI

SEE SHEET 16FJ

SEE SHEET 16FK

SEE SHEET 16FL

SEE SHEET 16FM

SEE SHEET 16FN

SEE SHEET 16FO

SEE SHEET 16FP

SEE SHEET 16FQ

SEE SHEET 16FR

SEE SHEET 16FS

SEE SHEET 16FT

SEE SHEET 16FU

SEE SHEET 16FV

SEE SHEET 16FW

SEE SHEET 16FX

SEE SHEET 16FY

SEE SHEET 16FZ

SEE SHEET 16GA

SEE SHEET 16GB

SEE SHEET 16GC

SEE SHEET 16GD

SEE SHEET 16GE

SEE SHEET 16GF

SEE SHEET 16GG

SEE SHEET 16GH

SEE SHEET 16GI

SEE SHEET 16GJ

SEE SHEET 16GK

SEE SHEET 16GL

SEE SHEET 16GM

SEE SHEET 16GN

SEE SHEET 16GO

SEE SHEET 16GP

SEE SHEET 16GQ

SEE SHEET 16GR

SEE SHEET 16GS

SEE SHEET 16GT

SEE SHEET 16GU

SEE SHEET 16GV

SEE SHEET 16GW

SEE SHEET 16GX

SEE SHEET 16GY

SEE SHEET 16GZ

SEE SHEET 16HA

SEE SHEET 16HB

SEE SHEET 16HC

SEE SHEET 16HD

SEE SHEET 16HE

SEE SHEET 16HF

SEE SHEET 16HG

SEE SHEET 16HH

SEE SHEET 16HI

SEE SHEET 16HJ

SEE SHEET 16HK

SEE SHEET 16HL

SEE SHEET 16HM

SEE SHEET 16HN

SEE SHEET 16HO

SEE SHEET 16HP

SEE SHEET 16HQ

SEE SHEET 16HR

SEE SHEET 16HS

SEE SHEET 16HT

SEE SHEET 16HU

SEE SHEET 16HV

SEE SHEET 16HW

SEE SHEET 16HX

SEE SHEET 16HY

SEE SHEET 16HZ

SEE SHEET 16IA

SEE SHEET 16IB

SEE SHEET 16IC

SEE SHEET 16ID

SEE SHEET 16IE

SEE SHEET 16IF

SEE SHEET 16IG

SEE SHEET 16IH

SEE SHEET 16II

SEE SHEET 16IJ

SEE SHEET 16IK

SEE SHEET 16IL

SEE SHEET 16IM

SEE SHEET 16IN

SEE SHEET 16IO

SEE SHEET 16IP

SEE SHEET 16IQ

SEE SHEET 16IR

SEE SHEET 16IS

SEE SHEET 16IT

SEE SHEET 16IU

SEE SHEET 16IV

SEE SHEET 16IW

SEE SHEET 16IX

SEE SHEET 16IY

SEE SHEET 16IZ

SEE SHEET 16JA

SEE SHEET 16JB

SEE SHEET 16JC

SEE SHEET 16JD

SEE SHEET 16JE

SEE SHEET 16JF

SEE SHEET 16JG

SEE SHEET 16JH

SEE SHEET 16JI

SEE SHEET 16JJ

SEE SHEET 16JK

SEE SHEET 16JL

SEE SHEET 16JM

SEE SHEET 16JN

SEE SHEET 16JO

SEE SHEET 16JP

SEE SHEET 16JQ

SEE SHEET 16JR

SEE SHEET 16JS

SEE SHEET 16JT

SEE SHEET 16JU

SEE SHEET 16JV

SEE SHEET 16JW

SEE SHEET 16JX

SEE SHEET 16JY

SEE SHEET 16JZ

SEE SHEET 16KA

SEE SHEET 16KB

SEE SHEET 16KC

SEE SHEET 16KD

SEE SHEET 16KE

SEE SHEET 16KF

SEE SHEET 16KG

SEE SHEET 16KH

SEE SHEET 16KI

SEE SHEET 16KJ

SEE SHEET 16KK

SEE SHEET 16KL

SEE SHEET 16KM

SEE SHEET 16KN

SEE SHEET 16KO

SEE SHEET 16KP

SEE SHEET 16KQ

SEE SHEET 16KR

SEE SHEET 16KS

SEE SHEET 16KT

SEE SHEET 16KU

SEE SHEET 16KV

SEE SHEET 16KW

SEE SHEET 16KX

SEE SHEET 16KY

SEE SHEET 16KZ

SEE SHEET 16LA

SEE SHEET 16LB

SEE SHEET 16LC

SEE SHEET 16LD

SEE SHEET 16LE

SEE SHEET 16LF

SEE SHEET 16LG

SEE SHEET 16LH

SEE SHEET 16LI

SEE SHEET 16LJ

SEE SHEET 16LK

SEE SHEET 16LL

SEE SHEET 16LM

SEE SHEET 16LN

SEE SHEET 16LO

SEE SHEET 16LP

SEE SHEET 16LQ

SEE SHEET 16LR

SEE SHEET 16LS

SEE SHEET 16LT

SEE SHEET 16LU

SEE SHEET 16LV

SEE SHEET 16LW

SEE SHEET 16LX

SEE SHEET 16LY

SEE SHEET 16LZ

SEE SHEET 16MA

SEE SHEET 16MB

SEE SHEET 16MC

SEE SHEET 16MD

SEE SHEET 16ME

SEE SHEET 16MF

SEE SHEET 16MG

SEE SHEET 16MH

SEE SHEET 16MI

SEE SHEET 16MJ

SEE SHEET 16MK

SEE SHEET 16ML

SEE SHEET 16MM

SEE SHEET 16MN

SEE SHEET 16MO

SEE SHEET 16MP

SEE SHEET 16MQ

SEE SHEET 16MR

SEE SHEET 16MS

SEE SHEET 16MT

SEE SHEET 16MU

SEE SHEET 16MV

SEE SHEET 16MW

SEE SHEET 16MX

SEE SHEET 16MY

SEE SHEET 16MZ

SEE SHEET 16NA

SEE SHEET 16NB

SEE SHEET 16NC

SEE SHEET 16ND

SEE SHEET 16NE

SEE SHEET 16NF

SEE SHEET 16NG

SEE SHEET 16NH

SEE SHEET 16NI

SEE SHEET 16NJ

SEE SHEET 16NK

SEE SHEET 16NL

SEE SHEET 16NM

SEE SHEET 16NN

SEE SHEET 16NO

SEE SHEET 16NP

SEE SHEET 16NQ

SEE SHEET 16NR

SEE SHEET 16NS

SEE SHEET 16NT

SEE SHEET 16NU

SEE SHEET 16NV

SEE SHEET 16NW

SEE SHEET 16NX

SEE SHEET 16NY

SEE SHEET 16NZ

SEE SHEET 16OA

SEE SHEET 16OB

SEE SHEET 16OC

SEE SHEET 16OD

SEE SHEET 16OE

SEE SHEET 16OF

SEE SHEET 16OG

SEE SHEET 16OH

SEE SHEET 16OI

SEE SHEET 16OJ

SEE SHEET 16OK

SEE SHEET 16OL

SEE SHEET 16OM

SEE SHEET 16ON

SEE SHEET 16OO

SEE SHEET 16OP

SEE SHEET 16OQ

SEE SHEET 16OR

SEE SHEET 16OS

SEE SHEET 16OT

SEE SHEET 16OU

SEE SHEET 16OV

SEE SHEET 16OW

SEE SHEET 16OX

SEE SHEET 16OY

SEE SHEET 16OZ

SEE SHEET 16PA

SEE SHEET 16PB

SEE SHEET 16PC

SEE SHEET 16PD

SEE SHEET 16PE

SEE SHEET 16PF

SEE SHEET 16PG

SEE SHEET 16PH

SEE SHEET 16PI

SEE SHEET 16PJ

SEE SHEET 16PK

SEE SHEET 16PL

SEE SHEET 16PM

SEE SHEET 16PN

SEE SHEET 16PO

SEE SHEET 16PP

SEE SHEET 16PQ

SEE SHEET 16PR

SEE SHEET 16PS

SEE SHEET 16PT

SEE SHEET 16PU

SEE SHEET 16PV

SEE SHEET 16PW

SEE SHEET 16PX

SEE SHEET 16PY

SEE SHEET 16PZ

SEE SHEET 16QA

SEE SHEET 16QB

SEE SHEET 16QC

SEE SHEET 16QD

SEE SHEET 16QE

SEE SHEET 16QF

SEE SHEET 16QG

SEE SHEET 16QH

SEE SHEET 16QI

SEE SHEET 16QJ

SEE SHEET 16QK

SEE SHEET 16QL

SEE SHEET 16QM

SEE SHEET 16QN

SEE SHEET 16QO

SEE SHEET 16QP

SEE SHEET 16QQ

SEE SHEET 16QR

SEE SHEET 16QS

SEE SHEET 16QT

SEE SHEET 16QU

SEE SHEET 16QV

SEE SHEET 16QW

SEE SHEET 16QX

SEE SHEET 16QY

SEE SHEET 16QZ

SEE SHEET 16RA

SEE SHEET 16RB

SEE SHEET 16RC

SEE SHEET 16RD

SEE SHEET 16RE

SEE SHEET 16RF

SEE SHEET 16RG

SEE SHEET 16RH

SEE SHEET 16RI

SEE SHEET 16RJ

SEE SHEET 16RK

SEE SHEET 16RL

SEE SHEET 16RM

SEE SHEET 16RN

SEE SHEET 16RO

SEE SHEET 16RP

SEE SHEET 16RQ

SEE SHEET 16RR

SEE SHEET 16RS

SEE SHEET 16RT

SEE SHEET 16RU

SEE SHEET 16RV

SEE SHEET 16RW

SEE SHEET 16RX

SEE SHEET 16RY

SEE SHEET 16RZ

SEE SHEET 16SA

SEE SHEET 16SB

SEE SHEET 16SC

SEE SHEET 16SD

SEE SHEET 16SE

SEE SHEET 16SF

SEE SHEET 16SG

SEE SHEET 16SH

SEE SHEET 16SI

SEE SHEET 16SJ

SEE SHEET 16SK

SEE SHEET 16SL

SEE SHEET 16SM

SEE SHEET 16SN

SEE SHEET 16SO

SEE SHEET 16SP

SEE SHEET 16SQ

SEE SHEET 16SR

SEE SHEET 16SS

SEE SHEET 16ST

SEE SHEET 16SU

SEE SHEET 16SV

SEE SHEET 16SW

SEE SHEET 16SX

SEE SHEET 16SY

SEE SHEET 16SZ

SEE SHEET 16TA

SEE SHEET 16TB

SEE SHEET 16TC

SEE SHEET 16TD

SEE SHEET 16TE

SEE SHEET 16TF

SEE SHEET 16TG

SEE SHEET 16TH

SEE SHEET 16TI

SEE SHEET 16TJ

SEE SHEET 16TK

SEE SHEET 16TL

SEE SHEET 16TM

SEE SHEET 16TN

SEE SHEET 16TO

SEE SHEET 16TP

SEE SHEET 16TQ

SEE SHEET 16TR

SEE SHEET 16TS

SEE SHEET 16TT

SEE SHEET 16TU

SEE SHEET 16TV

SEE SHEET 16TW

SEE SHEET 16TX

SEE SHEET 16TY

SEE SHEET 16TZ

SEE SHEET 16UA

SEE SHEET 16UB

SEE SHEET 16UC

SEE SHEET 16UD

SEE SHEET 16UE

SEE SHEET 16UF

SEE SHEET 16UG

SEE SHEET 16UH

SEE SHEET 16UI

SEE SHEET 16UJ

SEE SHEET 16UK

SEE SHEET 16UL

SEE SHEET 16UM

SEE SHEET 16UN

SEE SHEET 16UO

SEE SHEET 16UP

SEE SHEET 16UQ

SEE SHEET 16UR

SEE SHEET 16US

SEE SHEET 16UT

SEE SHEET 16UU

SEE SHEET 16UV

SEE SHEET 16UW

SEE SHEET 16UX

SEE SHEET 16UY

SEE SHEET 16UZ

SEE SHEET 16VA

SEE SHEET 16VB

SEE SHEET 16VC

SEE SHEET 16VD

SEE SHEET 16VE

SEE SHEET 16VF

SEE SHEET 16VG

SEE SHEET 16VH

SEE SHEET 16VI

SEE SHEET 16VJ

SEE SHEET 16VK

SEE SHEET 16VL

SEE SHEET 16VM

SEE SHEET 16VN

SEE SHEET 16VO

SEE SHEET 16VP

SEE SHEET 16VQ

SEE SHEET 16VR

SEE SHEET 16VS

SEE SHEET 16VT

SEE SHEET 16VU

SEE SHEET 16VV

SEE SHEET 16VW

SEE SHEET 16VX

SEE SHEET 16VY

SEE SHEET 16VZ

SEE SHEET 16WA

SEE SHEET 16WB

SEE SHEET 16WC

SEE SHEET 16WD

SEE SHEET 16WE

SEE SHEET 16WF

SEE SHEET 16WG

SEE SHEET 16WH

SEE SHEET 16WI

SEE SHEET 16WJ

SEE SHEET 16WK

SEE SHEET 16WL

SEE SHEET 16WM

SEE SHEET 16WN

SEE SHEET 16WO

SEE SHEET 16WP

SEE SHEET 16WQ

SEE SHEET 16WR

SEE SHEET 16WS

SEE SHEET 16WT

SEE SHEET 16WU

SEE SHEET 16WV

SEE SHEET 16WW

SEE SHEET 16WX

SEE SHEET 16WY

SEE SHEET 16WZ

SEE SHEET 16XA

SEE SHEET 16XB

SEE SHEET 16XC

SEE SHEET 16XD

SEE SHEET 16XE

SEE SHEET 16XF

SEE SHEET 16XG

SEE SHEET 16XH

SEE SHEET 16XI

SEE SHEET 16XJ

SEE SHEET 16XK

SEE SHEET 16XL

SEE SHEET 16XM

SEE SHEET 16XN

SEE SHEET 16XO

SEE SHEET 16XP

SEE SHEET 16XQ

SEE SHEET 16XR

SEE SHEET 16XS

SEE SHEET 16XT

SEE SHEET 16XU

SEE SHEET 16XV

SEE SHEET 16XW

SEE SHEET 16XX

SEE SHEET 16XY

SEE SHEET 16XZ

SEE SHEET 16YA

SEE SHEET 16YB

SEE SHEET 16YC

SEE SHEET 16YD

SEE SHEET 16YE

SEE SHEET 16YF

SEE SHEET 16YG

SEE SHEET 16YH

SEE SHEET 16YI

SEE SHEET 16YJ

SEE SHEET 16YK

SEE SHEET 16YL

SEE SHEET 16YM

SEE SHEET 16YN

SEE SHEET 16YO

SEE SHEET 16YP

SEE SHEET 16YQ

SEE SHEET 16YR

SEE SHEET 16YS

SEE SHEET 16YT

SEE SHEET 16YU

SEE SHEET 16YV

SEE SHEET 16YW

SEE SHEET 16YX

SEE SHEET 16YY

SEE SHEET 16YZ

SEE SHEET 16ZA

SEE SHEET 16ZB

SEE SHEET 16ZC

SEE SHEET 16ZD

SEE SHEET 16ZE

SEE SHEET 16ZF

SEE SHEET 16ZG

SEE SHEET 16ZH

SEE SHEET 16ZI

SEE SHEET 16ZJ

SEE SHEET 16ZK

SEE SHEET 16ZL

SEE SHEET 16ZM

SEE SHEET 16ZN

SEE SHEET 16ZO

SEE SHEET 16ZP

SEE SHEET 16ZQ

SEE SHEET 16ZR

SEE SHEET 16ZS

SEE SHEET 16ZT

SEE SHEET 16ZU

SEE SHEET 16ZV

SEE SHEET 16ZW

SEE SHEET 16ZX

SEE SHEET 16ZY

SEE SHEET 16ZZ

SEE SHEET 16AAA

SEE SHEET 16AAB

SEE SHEET 16AAC

SEE SHEET 16AAD

SEE SHEET 16AAE

SEE SHEET 16AAF

SEE SHEET 16AAG

SEE SHEET 16AAH

SEE SHEET 16AAI

SEE SHEET 16AAJ

SEE SHEET 16AAK

SEE SHEET 16AAL

SEE SHEET 16AAM

SEE SHEET 16AAN

SEE SHEET 16AAO

SEE SHEET 16AAP

SEE SHEET 16AAQ

SEE SHEET 16AAR

SEE SHEET 16AAS

SEE SHEET 16AAT

SEE SHEET 16AAU

SEE SHEET 16AAV

SEE SHEET 16AAW

SEE SHEET 16AAX

SEE SHEET 16AAY

SEE SHEET 16AAZ

SEE SHEET 16ABA

SEE SHEET 16ABB

SEE SHEET 16ABC

SEE SHEET 16ABD

SEE SHEET 16ABE

SEE SHEET 16ABF

SEE SHEET 16ABG

SEE SHEET 16ABH

SEE SHEET 16ABI

SEE SHEET 16ABJ

SEE SHEET 16ABK

SEE SHEET 16ABL

SEE SHEET 16ABM

SEE SHEET 16ABN

SEE SHEET 16ABO

SEE SHEET 16ABP

SEE SHEET 16ABQ

SEE SHEET 16ABR

SEE SHEET 16ABS

SEE SHEET 16ABT

SEE SHEET 16ABU

SEE SHEET 16ABV

SEE SHEET 16ABW

SEE SHEET 16ABX

SEE SHEET 16ABY

SEE SHEET 16ABZ

SEE SHEET 16ACA

SEE SHEET 16ACB

SEE SHEET 16ACC

SEE SHEET 16ACD

SEE SHEET 16ACE

SEE SHEET 16ACF

SEE SHEET 16ACG

SEE SHEET 16ACH

SEE SHEET 16ACI

SEE SHEET 16ACJ

SEE SHEET 16ACK

SEE SHEET 16ACL

SEE SHEET 16ACM

SEE SHEET 16ACN

SEE SHEET 16ACO

SEE SHEET 16ACP

SEE SHEET 16ACQ

SEE SHEET 16ACR

SEE SHEET 16ACS

SEE SHEET 16ACT

SEE SHEET 16ACU

SEE SHEET 16ACV

SEE SHEET 16ACW

SEE SHEET 16ACX

SEE SHEET 16ACY

SEE SHEET 16ACZ

SEE SHEET 16ADA

SEE SHEET 16ADB

SEE SHEET 16ADC

SEE SHEET 16ADD

SEE SHEET 16ADE

SEE SHEET 16ADF

SEE SHEET 16ADG

SEE SHEET 16ADH

SEE SHEET 16ADI

SEE SHEET 16ADJ

SEE SHEET 16ADK

SEE SHEET 16ADL

SEE SHEET 16ADM

SEE SHEET 16ADN

SEE SHEET 16ADO

SEE SHEET 16ADP

SEE SHEET 16ADQ

SEE SHEET 16ADR

SEE SHEET 16ADS

SEE SHEET 16ADT

SEE SHEET 16ADU

SEE SHEET 16ADV

SEE SHEET 16ADW

SEE SHEET 16ADX

SEE SHEET 16ADY

SEE SHEET 16ADZ

SEE SHEET 16AEA

SEE SHEET 16AEB

SEE SHEET 16AEC

SEE SHEET 16AED

SEE SHEET 16AEE

SEE SHEET 16AEF

SEE SHEET 16AEG

SEE SHEET 16AEH

SEE SHEET 16AEI

SEE SHEET 16AEJ

SEE SHEET 16AEK

SEE SHEET 16AEL

SEE SHEET 16AEM

SEE SHEET 16AEN

SEE SHEET 16AEO

SEE SHEET 16AEP

SEE SHEET 16AEQ

SEE SHEET 16AER

SEE SHEET 16AES

SEE SHEET 16AET

SEE SHEET 16AEU

SEE SHEET 16AEV

SEE SHEET 16AEW

SEE SHEET 16AEX

SEE SHEET 16AEY

SEE SHEET 16AEZ

SEE SHEET 16AFA

SEE SHEET 16AFB

SEE SHEET 16AFC

SEE SHEET 16AFD

SEE SHEET 16AFE

SEE SHEET 16AFF

SEE SHEET 16AFG

SEE SHEET 16AFH

SEE SHEET 16AFI

SEE SHEET 16AFJ

SEE SHEET 16AFK

SEE SHEET 16AFL

SEE SHEET 16AFM

SEE SHEET 16AFN

SEE SHEET 16AFO

SEE SHEET 16AFP

SEE SHEET 16AFQ

SEE SHEET 16AFR

SEE SHEET 16AFS

SEE SHEET 16AFT

SEE SHEET 16AFU

SEE SHEET 16AFV

SEE SHEET 16AFW

SEE SHEET 16AFX

SEE SHEET 16AFY

SEE SHEET 16AFZ

SEE SHEET 16AGA

SEE SHEET 16AGB

SEE SHEET 16AGC

SEE SHEET 16AGD

SEE SHEET 16AGE

SEE SHEET 16AGF

SEE SHEET 16AGG

SEE SHEET 16AGH

SEE SHEET 16AGI

SEE SHEET 16AGJ

SEE SHEET 16AGK

SEE SHEET 16AGL

SEE SHEET 16AGM

SEE SHEET 16AGN

SEE SHEET 16AGO

SEE SHEET 16AGP

SEE SHEET 16AGQ

SEE SHEET 16AGR

SEE SHEET 16AGS

SEE SHEET 16AGT

SEE SHEET 16AGU

SEE SHEET 16AGV

SEE SHEET 16AGW

SEE SHEET 16AGX

SEE SHEET 16AGY

SEE SHEET 16AGZ

SEE SHEET 16AHA

SEE SHEET 16AHB

SEE SHEET 16AHC

SEE SHEET 16AHD

SEE SHEET 16AHE

SEE SHEET 16AHF

SEE SHEET 16AHG

SEE SHEET 16AHH

SEE SHEET 16AHI

SEE SHEET 16AHJ

SEE SHEET 16AHK

SEE SHEET 16AHL

SEE SHEET 16AHM

SEE SHEET 16AHN

SEE SHEET 16AHO

SEE SHEET 16AHP

SEE SHEET 16AHQ

SEE SHEET 16AHR

SEE SHEET 16AHS

SEE SHEET 16AHT

SEE SHEET 16AHU

SEE SHEET 16AHV

SEE SHEET 16AHW

SEE SHEET 16AHX

SEE SHEET 16AHY

SEE SHEET 16AHZ

SEE SHEET 16AIA

SEE SHEET 16AIB

SEE SHEET 16AIC

SEE SHEET 16AID

SEE SHEET 16AIE

SEE SHEET 16AIF

SEE SHEET 16AIG

SEE SHEET 16AIH

SEE SHEET 16AII

SEE SHEET 16AIJ

SEE SHEET 16AIK

SEE SHEET 16AIL

SEE SHEET 16AIM

SEE SHEET 16AIN

SEE SHEET 16AIO

SEE SHEET 16AIP

SEE SHEET 16AIQ

SEE SHEET 16AIR

SEE SHEET 16AIS

SEE SHEET 16AIT

SEE SHEET 16AIU

SEE SHEET 16AIV

SEE SHEET 16AIW

SEE SHEET 16AIX

SEE SHEET 16AIY

SEE SHEET 16AIZ

SEE SHEET 16AJA

SEE SHEET 16AJB

SEE SHEET 16AJC

SEE SHEET 16AJD

SEE SHEET 16AJE

SEE SHEET 16AJF

SEE SHEET 16AJG

SEE SHEET 16AJH

SEE SHEET 16AJI

SEE SHEET 16AJJ

SEE SHEET 16AJK

SEE SHEET 16AJL

SEE SHEET 16AJM

SEE SHEET 16AJN

SEE SHEET 16AJO

SEE SHEET 16AJP

SEE SHEET 16AJQ

SEE SHEET 16AJR

SEE SHEET 16AJS

SEE SHEET 16AJT

SEE SHEET 16AJU

SEE SHEET 16AJV

SEE SHEET 16AJW

SEE SHEET 16AJX

SEE SHEET 16AJY

SEE SHEET 16AJZ

SEE SHEET 16AKA

SEE SHEET 16AKB

SEE SHEET 16AKC

SEE SHEET 16AKD

SEE SHEET 16AKE

SEE SHEET 16AKF

SEE SHEET 16AKG

SEE SHEET 16AKH

SEE SHEET 16AKI

SEE SHEET 16AKJ

SEE SHEET 16AKK

SEE SHEET 16AKL

SEE SHEET 16AKM

SEE SHEET 16AKN

SEE SHEET 16AKO

SEE SHEET 16AKP

SEE SHEET 16AKQ

SEE SHEET 16AKR

SEE SHEET 16AKS

SEE SHEET 16AKT

SEE SHEET 16AKU

SEE SHEET 16AKV

SEE SHEET 16AKW

SEE SHEET 16AKX

SEE SHEET 16AKY

SEE SHEET 16AKZ

SEE SHEET 16ALA

SEE SHEET 16ALB

SEE SHEET 16ALC

SEE SHEET 16ALD

SEE SHEET 16ALE

SEE SHEET 16ALF

SEE SHEET 16ALG

SEE SHEET 16ALH

SEE SHEET 16ALI

SEE SHEET 16ALJ

SEE SHEET 16ALK

SEE SHEET 16ALL

SEE SHEET 16ALM

SEE SHEET 16ALN

SEE SHEET 16ALO

SEE SHEET 16ALP

SEE SHEET 16ALQ

SEE SHEET 16ALR

SEE SHEET 16ALS

SEE SHEET 16ALT

SEE SHEET 16ALU

SEE SHEET 16ALV

SEE SHEET 16ALW

SEE SHEET 16ALX

SEE SHEET 16ALY

SEE SHEET 16ALZ

SEE SHEET 16AMA

SEE SHEET 16AMB

SEE SHEET 16AMC

SEE SHEET 16AMD

SEE SHEET 16AME

SEE SHEET 16AMF

SEE SHEET 16AMG

SEE SHEET 16AMH

SEE SHEET 16AMI

SEE SHEET 16AMJ

SEE SHEET 16AMK

SEE SHEET 16AML

SEE SHEET 16AMM

SEE SHEET 16AMN

SEE SHEET 16AMO

SEE SHEET 16AMP

SEE SHEET 16AMQ

SEE SHEET 16AMR

SEE SHEET 16AMS

SEE SHEET 16AMT

SEE SHEET 16AMU

SEE SHEET 16AMV

SEE SHEET 16AMW

SEE SHEET 16AMX

SEE SHEET 16AMY

SEE SHEET 16AMZ

SEE SHEET 16ANA

SEE SHEET 16ANB

SEE SHEET 16ANC

SEE SHEET 16AND

SEE SHEET 16ANE

SEE SHEET 16ANF

SEE SHEET 16ANG

SEE SHEET 16ANH

SEE SHEET 16ANI

SEE SHEET 16ANJ

SEE SHEET 16ANK

SEE SHEET 16ANL

SEE SHEET 16ANM

SEE SHEET 16ANN

SEE SHEET 16ANO

SEE SHEET 16ANP

SEE SHEET 16ANQ

SEE SHEET 16ANR

SEE SHEET 16ANS

SEE SHEET 16ANT

SEE SHEET 16ANU

SEE SHEET 16ANV

SEE SHEET 16ANW

SEE SHEET 16ANX

SEE SHEET 16ANY

SEE SHEET 16ANZ

SEE SHEET 16AOA

SEE SHEET 16AOB

SEE SHEET 16AOC

SEE SHEET 16AOD

SEE SHEET 16AOE

SEE SHEET 16AOF

SEE SHEET 16AOG

SEE SHEET 16AOH

SEE SHEET 16AOI

SEE SHEET 16AOJ

SEE SHEET 16AOK

SEE SHEET 16AOL

SEE SHEET 16AOM

SEE SHEET 16AON

SEE SHEET 16AOO

SEE SHEET 16AOP

SEE SHEET 16AOQ

SEE SHEET 16AOR

SEE SHEET 16AOS

SEE SHEET 16AOT

SEE SHEET 16AOU

SEE SHEET 16AOV

SEE SHEET 16AOW

SEE SHEET 16AOX

SEE SHEET 16AOY

SEE SHEET 16AOZ

SEE SHEET 16APA

SEE SHEET 16APB

SEE SHEET 16APC

SEE SHEET 16APD

SEE SHEET 16APE

SEE SHEET 16APF

SEE SHEET 16APG

SEE SHEET 16APH

SEE SHEET 16API

SEE SHEET 16APJ

SEE SHEET 16APK

SEE SHEET 16APL

SEE SHEET 16APM

SEE SHEET 16APN

SEE SHEET 16APO

SEE SHEET 16APP

SEE SHEET 16APQ

SEE SHEET 16APR

SEE SHEET 16APS

SEE SHEET 16APT

SEE SHEET 16APU

SEE SHEET 16APV

SEE SHEET 16APW

SEE SHEET 16APX

SEE SHEET 16APY

SEE SHEET 16APZ

SEE SHEET 16AQA

SEE SHEET 16AQB

SEE SHEET 16AQC

SEE SHEET 16AQD

SEE SHEET 16AQE

SEE SHEET 16AQF

SEE SHEET 16AQG

SEE SHEET 16AQH

SEE SHEET 16AQI

SEE SHEET 16AQJ

SEE SHEET 16AQK

SEE SHEET 16AQL

SEE SHEET 16AQM

SEE SHEET 16AQN

SEE SHEET 16AQO

SEE SHEET 16AQP

SEE SHEET 16AQQ

SEE SHEET 16AQR

SEE SHEET 16AQS

SEE SHEET 16AQT

SEE SHEET 16AQU

SEE SHEET 16AQV

SEE SHEET 16AQW

SEE SHEET 16AQX

SEE SHEET 16AQY

SEE SHEET 16AQZ

SEE SHEET 16ARA

SEE SHEET 16ARB

SEE SHEET 16ARC

SEE SHEET 16ARD

SEE SHEET 16ARE

SEE SHEET 16ARF

SEE SHEET 16ARG

SEE SHEET 16ARH

SEE SHEET 16ARI

SEE SHEET 16ARJ

SEE SHEET 16ARK

SEE SHEET 16ARL

SEE SHEET 16ARM

SEE SHEET 16ARN

SEE SHEET 16ARO

SEE SHEET 16ARP

SEE SHEET 16ARQ

SEE SHEET 16ARR

SEE SHEET 16ARS

SEE SHEET 16ART

SEE SHEET 16ARU

SEE SHEET 16ARV

SEE SHEET 16ARW

SEE SHEET 16ARX

SEE SHEET 16ARY

SEE SHEET 16ARZ

SEE SHEET 16ASA

SEE SHEET 16ASB

SEE SHEET 16ASC

SEE SHEET 16ASD

SEE SHEET 16ASE

SEE SHEET 16ASF

SEE SHEET 16ASG

SEE SHEET 16ASH

SEE SHEET 16ASI

SEE SHEET 16ASJ

SEE SHEET 16ASK

SEE SHEET 16ASL

SEE SHEET 16ASM

SEE SHEET 16ASN

SEE SHEET 16ASO

SEE SHEET 16ASP

SEE SHEET 16ASQ

SEE SHEET 16ASR

SEE SHEET 16ASS

SEE SHEET 16AST

SEE SHEET 16ASU

SEE SHEET 16ASV

SEE SHEET 16ASW

SEE SHEET

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL
SOIL EROSION AND SEDIMENT CONTROL PLAN
BLOCK 93, LOTS 19, 20, 45.01, 46 & 60
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

SHEET No. 16J OF

Bowman Consulting Group Ltd
3 Paragon Way, Suite 120
Freehold, New Jersey 07728
E-mail: NJ@bowman.com
Phone: 732-665-6500
FAX: 732-665-6501
NJ Certificate of Authorization No. 24GA28222600

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

Bowman

REVISION	DATE	CHK'D
1 REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD
2 REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
3 REVISED PER ENGINEERING REVIEW	2/14/25	SAD
4 REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
5		
6		
7		
8		
9		
10		
11		
12		

PB01_081391-01-001
DATE: 06/25/2024
CHK'D: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE BY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. IS NOT TO BE USED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP, LTD.
© 2025 BOWMAN CONSULTING GROUP, LTD.
ALL RIGHTS RESERVED

SEE SHEET I
SEE SHEET J
SEE SHEET O
ROAD F
ROAD E
ROAD 9
ROAD 7
ROAD 6
CHANGE ROAD 9 PROFILE TO MATCH THESE ELEVATIONS
TEMP STOCKPILE LOCATION (TYP.)
INLET PROTECTION (TYP.)
SILT FENCE (TYP.)
LIMIT OF DISTURBANCE (TYP.)
SCALE: 1"=30'
S02°19'27"E - 10.57'

XREFS: 081391_FGR0.dwg
081077.01 Deer Valley-Hopewell-sheets 2-13.dwg
081391_PBASE.dwg
Deer Valley Easement.dwg

PageSetup: ---- PlotStyleTable: BCG-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:46:07AM, dno.sheikh, LAYOUT:SHT-16J

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL
SOIL EROSION AND SEDIMENT CONTROL PLAN
BLOCK 33, LOTS 19, 20, 45.01, 46 & 60
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

SHEET No. 16K OF

Bowman Consulting Group Ltd
3 Paragon Way, Suite 120
Freehold, New Jersey 07728
E-mail: NJ@bowman.com
Phone: 732-665-6500
FAX: 732-665-6501
Owner/Developer or Authorized Person
NJ Certificate of Authorization No. 24GA28222600
SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

Bowman

THESE DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THIS DRAWING OR ANY PORTION THEREOF MAY NOT BE REPRODUCED OR USED FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP, LTD. UPON FOR ANY OTHER PURPOSE
© 2025 BOWMAN CONSULTING GROUP, LTD
ALL RIGHTS RESERVED

PROJ.: 081391-01-001
DATE: 06/25/2024
CHKD: SAD

REVISION	DATE	CHKD
1 REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD
2 REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
3 REVISED PER ENGINEERING REVIEW	2/14/25	SAD
4 REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
5		
6		
7		
8		
9		
10		
11		
12		

XREFS: 081391_FGRD.dwg
081077.01 Deer Valley-Hopewell-sheets 2-13.dwg
081391_PBASE.dwg
Deer Valley Easement.dwg

PageSetup---- PlotStyleTable: BCC-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:47:09AM, dno.splihlt, LAYOUT:SHT-16K

PageSetUp: ----- PlotStyleTable: BCG-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:48:17AM, dino.spinelli, LAYOUT:SHT-16L

XREFS: 081391_PGRD.dwg
081077.01 Deer Valley-Hopewell-sheets 2-13.dwg
081391_PBASE.dwg
Deer Valley Easement.dwg

LIMIT OF DISTURBANCE (TYP.)

SILT FENCE (TYP.)

INLET PROTECTION (TYP.)

ROAD 2
(TO BE DEDICATED AS PUBLIC STREET)
(60' ROW)

ROAD 3
(TO BE DEDICATED AS PUBLIC STREET)
(60' ROW)

ROAD 6
(TO BE DEDICATED AS PUBLIC STREET)
(60' ROW)

ROAD C
(TO BE DEDICATED AS PUBLIC STREET)
(60' ROW)

TEMP. STOCKPILE LOCATION (TYP.)

SEE SHEET K

SEE SHEET M

SEE SHEET N

SEE SHEET O

SHEET No. 16L OF

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR

VENUE AT HOPEWELL

SOIL EROSION AND SEDIMENT CONTROL PLAN

BLOCK 93, LOTS 19, 20, 45.01, 46 & 60

TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

Bowman Consulting Group Ltd
3 Paragon Way, Suite 170
Freehold, New Jersey 07728
bowman.com
E-mail: NJ@Bowman.com

Phone: 732-665-5500
FAX: 732-665-5501
NJ Certificate of Authorization No. 24GA28222600

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100

Bowman

PROJ.: 081391-01-001
DATE: 06/25/2024
CHKD: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THIS DRAWING MAY NOT BE COPIED, REUSED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY PURPOSE WHATSOEVER WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP, LTD.
© 2025 BOWMAN CONSULTING GROUP LTD
ALL RIGHTS RESERVED

No.	REVISION	DATE	CHKD
6			
5			
4	REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
3	REVISED PER ENGINEERING REVIEW	2/14/25	SAD
2	REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
1	REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD

No.	REVISION	DATE	CHKD
12			
11			
10			
9			
8			
7			

PageSetUp: ----- PlotStyleTable: BCG-NJ.ctb
V:\081391 - Nursery Road-Hopewell\081391-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\081391-SP-SESC.dwg 04/01/25 11:49:16AM, dino.spinelli, LAYOUT:SHT-16M

XREFS: 081391_PGRD.dwg
081037.01 Deer Valley-Hopewell-sheets 2-13.dwg
Deer Valley Easement.dwg

INLET PROTECTION (TYP.)

ROAD 2
(TO BE DEDICATED AS PUBLIC STREET)
(50' R.O.W.)

ROAD 4
(TO BE DEDICATED AS PUBLIC STREET)
(50' R.O.W.)

ROAD 5
(TO BE DEDICATED AS PUBLIC STREET)
(50' R.O.W.)

SILT FENCE (TYP.)

LIMIT OF DISTURBANCE (TYP.)

TEMP. STOCKPILE LOCATION (TYP.)

SEE SHEET 17

SEE SHEET 15

SCALE: 1"=30'

0 30 60 120 ft.

SHEET No. 16M OF	PRELIMINARY AND FINAL MAJOR SUBDIVISION & PRELIMINARY AND FINAL SITE PLAN FOR VENUE AT HOPEWELL SOIL EROSION AND SEDIMENT CONTROL PLAN BLOCK 93, LOTS 19, 20, 45.01, 46 & 60 TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY	Bowman Consulting Group Ltd 3 Paragon Way, Suite 170 Freehold, New Jersey 07728 bowman.com E-mail: NJ@Bowman.com Phone: 732-665-5500 FAX: 732-665-5501 NJ Certificate of Authorization No. 24GA28222600 SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04447100	Bowman

PROJ.: 081391-01-001
DATE: 06/25/2024
CHKD: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THIS DRAWING MAY NOT BE COPIED, REUSED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF BOWMAN CONSULTING GROUP LTD.
© 2025 BOWMAN CONSULTING GROUP LTD.
ALL RIGHTS RESERVED

	REVISION	DATE	CHKD
6			
5			
4	REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
3	REVISED PER ENGINEERING REVIEW	2/14/25	SAD
2	REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
1	REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD

	REVISION	DATE	CHKD
12			
11			
10			
9			
8			
7			



NO.	REVISION	DATE	CHKD
1	REVISED PER RSI COMPLETENESS REVIEW	09/10/24	SAD
2	REVISED PER TOWNSHIP COMMENTS	12/18/24	SAD
3	REVISED PER ENGINEERING REVIEW	2/14/25	SAD
4	REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
5			
6			
7			
8			
9			
10			
11			
12			

PROJ.: 08139-101-001
DWG.: 08139-16N24
CHKD: SAD

THE DRAWINGS AND ALL INFORMATION CONTAINED THEREIN ARE THE PROPERTY OF THE WORK WAS CONTRACTED, OR IN PART, FOR A SPECIFIC PROJECT AND MAY NOT BE COPIED, REUSED, DISCLOSED, LENT OR ASSIGNED TO ANY OTHER PARTY OR USED FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN AUTHORIZATION OF BOWMAN CONSULTING GROUP, LTD. © BOWMAN CONSULTING GROUP, LTD. ALL RIGHTS RESERVED

Bowman

Bowman Consulting Group Ltd
Suite 101, Building 2
Freehold, New Jersey 07728
www.bowman.com
Email: NJ@bowman.com

Phone: 732-665-5500
FAX: 732-665-5501
N.J. Certificate of Authorization
No. 24GA28222600

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04477100

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR

VENUE AT HOPEWELL

SOIL EROSION AND SEDIMENT CONTROL PLAN

BLOCK 58, LOTS 19.02, 20, 20.01, 44 & 49

TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

SHEET No.
16N
OF

XREFs: 08139-Topo.dwg
08139-Site Base Map.dwg
08139-Site Plan.dwg
Deer Valley Easement.dwg

PageSetUp: ---- PlotStyleTable: BCG-NJ.ctb
V:\08139\ - Nursery Road-Hopewell\08139-01-001 (ENG) - Venue at Hopewell SP\Engineering\Engineering Plans\02 Site Plans\08139-SP-SESC.dwg 04/01/25 11:51:17AM, dino.spinelli, LAYOUT SHT-16N

CONSTRUCTION SEQUENCE

SITE PREPARATION	DURATION
1. INSTALL SEDIMENT FILTER FENCE, TREE PROTECTION FENCE, AND FENCING ALONG LIMITS OF DISTURBANCE.	4 WEEKS
2. INSTALL STABILIZED CONSTRUCTION ACCESS.	2 DAYS
3. CLEAR TREES AND REMOVE TREE STUMPS	4 WEEKS
4. REMOVE EXISTING BUILDINGS, PAVED AND GRAVEL DRIVES.	2 WEEKS
5. STRIP AND STOCKPILE TOPSOIL	1 WEEK
6. ROUGH GRADE SITE AND STORMWATER MANAGEMENT BASINS	8 WEEKS
7. PLACE CONSTRUCTION TRAILER AND CONSTRUCT STAGING AND LAYDOWN AREA. INSTALL STONE BEDDING OVER AREA FOR STABILIZATION DURING CONSTRUCTION OF SITE.	2 WEEKS
8. FINALIZE INTERIM CONSTRUCTION OF STORMWATER MANAGEMENT BASINS AND PROVIDE PERMANENT STABILIZATION PRIOR TO INSTALLATION OF STORM DRAINS. K3 SOIL AND SAND LAYERS IN BOTTOM OF BASINS NOT TO BE INSTALLED IN INTERIM CONDITION. BASIN BOTTOMS TO BE COVERED WITH ANCHORED DOWN FILTER FABRIC.	2 WEEKS
9. CONSTRUCT STORMWATER STRUCTURES AND PIPING, AND OUTFALLS AND SOIL EROSION AND SEDIMENT CONTROL MEASURES. STABILIZE BASINS UPON COMPLETION	12 WEEKS
10. ROUGH GRADE PROPOSED ROADWAYS ONSITE AND INSTALL CURB AND ROADWAY SUBBASE.	8 WEEKS
11. INSTALL ONSITE SANITARY SEWER AND WATER MAINS WITHIN ROADS. INSTALL WATER SERVICE AND SANITARY SEWER LATERALS FROM MAINS WITHIN PROPOSED ROADWAYS BEHIND CURB LINE LOCATION.	12 WEEKS
12. CONSTRUCT ROADWAY WIDENING ALONG WASHINGTON CROSSING - PENNINGTON ROAD: INSTALL CURB, SAWCUT PAVEMENT, ROUGH GRADE WIDENING AREA TO SUBGRADE ELEVATIONS.	2 WEEKS
13. FINE GRADE WASHINGTON CROSSING - PENNINGTON ROAD ROADWAY WIDENING: CONSTRUCT ROADWAY SUBBASE, BASE COURSE.	2 WEEKS
14. FINE GRADE ONSITE ROADWAYS AND PARKING AREAS: CONSTRUCT ROADWAY BASE COURSE PAVEMENT.	4 WEEKS
15. CONSTRUCT SIDEWALKS.	4 WEEKS
16. INSTALL ELECTRIC, TELEPHONE, CABLE, GAS UTILITIES.	8 WEEKS
17. FINE GRADE LANDSCAPE AREAS AND OPEN SPACE LOTS.	6 WEEKS
18. INSTALL BUFFER LANDSCAPING AND STREET TREES ALONG ROADWAYS. INSTALL LIGHTING FIXTURES AND STREET LIGHTS.	12 WEEKS
19. SOIL RESTORATION AND TESTING FOR SITE PRIOR TO INSTALLATION OF TOPSOIL	2 WEEKS
20. TOP SOIL AND SEED ALL DISTURBED LANDSCAPED AREAS IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS.	4 WEEKS
21. INSTALL TRAFFIC SIGNS AND TEMPORARY STRIPING.	8 WEEKS
22. CONSTRUCT DWELLING UNITS AND AFFORDABLE HOUSING BUILDINGS.	ONGOING
23. UPON COMPLETION OF ALL RESIDENTIAL BUILDINGS ALONG A ROADWAY, CONSTRUCT FINAL PAVEMENT SURFACE COURSE AND INSTALL FINAL PAVEMENT STRIPING.	8 WEEKS
TYPICAL BUILDING CONSTRUCTION	
1. INSTALL SEDIMENT FILTER FENCE AROUND LOT PERIMETER INSTALL STABILIZED CONSTRUTION ENTRANCE FOR EACH LOT AT A DRIVEWAY LOCATION.	1 WEEK 2 WEEKS
2. INSTALL BUILDING FOUNDATION	1 WEEK
3. INSTALL UTILITY CONNECTIONS TO BUILDING.	8-12 WEEKS
4. CONSTRUCT BUILDING	1 WEEK
5. FINE GRADE LOT WITHIN LIMITS OF CLEARING/DISTURBANCE	1 WEEK
6. REMOVE STABILIZED CONSTRUCTION ACCESS AND CONSTRUCT DRIVEWAY, SIDEWALK AND PATIO.	1 WEEK
7. INSTALL PROPOSED LANDSCAPING ON LOT AND TOPSOIL, FERTILIZE AND SEED ALL DISTURBED AREAS IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS.	1 DAY
8. REMOVE ACCUMULATED SEDIMENT AND FILTER FABRIC FENCE ON INDIVIDUAL LOT ONLY. (REPEAT TYPICAL LOT CONSTRUCTION FOR EACH LOT AT TIME OF DEVELOPMENT)	
FINAL MEASURES AFTER FULL BUILD OUT OF DEVELOPMENT	2 WEEKS
1. REMOVE ALL ACCUMULATED SEDIMENT FROM ROADWAYS, AND STORMWATER BASINS, STORM PIPING AND AT BASIN OUTFALLS. REMOVE ANCHORED FILTER FABRIC FROM STORMWATER BASINS. K3 SOIL AND SAND LAYERS TO BE INSTALLED WITHIN BASINS.	1 WEEK
2. REMOVE ALL PERIMETER FILTER FABRIC FENCING AND TREE PROTECTION FENCING, AND ALL REMAINING INLET FILTER PROTECTION.	



TOPSOIL STOCK PILE DETAIL
NOT TO SCALE



NOTE:
SNOW FENCE IS TO BE LOCATED 10' FROM THE OUTER PERIMETER OF THE DRIP LINE. IN NO CASE SHALL IT BE CLOSER THAN 10' TO THE TRUNK. NO CONSTRUCTION MATERIALS, FILL, TOPSOIL, SOIL, ETC. SHALL BE STORED INSIDE THIS FENCE. EXISTING ELEVATIONS WITHIN THE FENCING AREA SHALL REMAIN UNCHANGED AND SOIL SHALL BE LEFT UNDISTURBED. (TO BE USED FOR SPECIMEN TREES IF IN THE VICINITY OF CLEARING OPERATION)

TREE PROTECTION
NOT TO SCALE



SILT FENCE DETAIL
NOT TO SCALE



NOTES

STONE SIZE: 1 1/2" - 2 1/2" CRUSHED STONE

WIDTH NOT LESS THAN FULL WIDTH AT POINTS OF EGRESS AND INGRESS.

WASHING: WHEN NECESSARY, WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC R.O.W.. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE WHICH DRAINS INTO AN APPROVED SEDIMENT BASIN.

MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC R.O.W., THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED, OR TRAPPED ONTO PUBLIC R.O.W. MUST BE REMOVED IMMEDIATELY.

WHEN THE CONSTRUCTION ACCESS EXITS ONTO A MAJOR ROADWAY, A PAVED TRANSITION AREA MAY BE INSTALLED BETWEEN THE MAJOR ROADWAY AND THE STONED ENTRANCE TO PREVENT LOOSE STONES FROM BEING TRANSPORTED OUT ONTO THE ROADWAY BY HEAVY EQUIPMENT ENTERING OR LEAVING THE SITE.

PERCENT SLOPE OF ROADWAY	LENGTH OF STONE REQUIRED	
	COARSE GRAINED SOILS	FINE GRAINED SOILS
0 TO 2%	50 ft.	100ft.
2 TO 5%	100ft.	200ft.
>5%	ENTIRE SURFACE STABILIZED WITH FABC BASE COURSE [1]	

1. AS PRESCRIBED BY LOCAL ORDINANCE OR OTHER GOVERNING AUTHORITY

STABILIZED CONSTRUCTION ENTRANCE
NOT TO SCALE

REMOVABLE PUMPING STATION
(LONG DURATION DEWATERING)

SUMP PIT
(SHORT DURATION DEWATERING)



SECTION A–A

PREFORMED SCOUR HOLE DETAIL
NOT TO SCALE



INLET PROTECTION TYPE "B"
N.T.S.



INLET PROTECTION
N.T.S.



SCOUR HOLE LOCATION	PIPE SIZE (IN.)	RIPRAP d50 (IN.)	DEPTH (FT.)	L1 (FT.)	L2 (FT.)	L3 (FT.)	W1 (FT.)	W2 (FT.)	W3 (FT.)
FES A100	30	6	1.25	15	7.5	3.75	12.5	5	3.75
FES A200	18	6	0.75	9	4.5	2.25	7.5	3	2.25
FES A300	18	6	0.75	9	4.5	2.25	7.5	3	2.25
FES A400	18	6	0.75	9	4.5	2.25	7.5	3	2.25
HW A01	24	6	1.0	12	6	3	10	4	3
FES B100	24	6	1.0	12	6	3	10	4	3
HW B200	42	6	1.75	21	10.5	5.25	17.5	7	5.25
HW B300	29 X 45	6	1.21	14.6	7.25	3.67	14.8	7.5	3.65
FES B01	30	6	1.25	15	7.5	3.75	12.5	5	3.75
FES C100	18	6	0.75	9	4.5	2.25	7.5	3	2.25
FES C200	36	6	1.50	18	9	4.5	15	6	4.5
HW C01	18	6	0.75	9	4.5	2.25	7.5	3	2.25
HW D100	24	6	1.0	12	6	3	10	4	3
FES E102	24	6	1.0	12	6	3	10	4	3
FES E101	18	6	0.75	9	4.5	2.25	7.5	3	2.25
FES E100	18	6	0.75	9	4.5	2.25	7.5	3	2.25
FES F100	15	6	0.63	7.8	3.75	1.92	6.3	2.5	1.9

NOTE:
RIPRAP SHALL CONFORM TO "STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY."

PREFORMED SCOUR HOLE DIMENSIONS



INLET SEDIMENT CONTROL DEVICE WITH CURB DEFLECTOR
NOT TO SCALE





SILTSACK® IS MANUFACTURED BY ACF. INSTALLATION AND MAINTENANCE SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

NOTE: TO BE INSTALLED ONCE CASTINGS HAVE BEEN BROUGHT TO GRADE AND MORTARED IN PLACE.

INLET SEDIMENT CONTROL DEVICE
NOT TO SCALE



SLOPE STABILIZATION MATTING
(LANDLOK TRM 1060 OR APPROVED EQUAL)
N.T.S.

hydraulic, biological, aesthetic and other environmental functions of the stream.

Soil Management and Preparation

Subgrade soils prior to the application of topsoil shall be free of excessive compaction to a depth of 6.0 inches to enhance the establishment of permanent vegetative cover.

This section of this Standard addresses the potential for excessive soil compaction in light of the intended land use, testing for excessive soil compaction where permanent vegetation is to be established and mitigation of excessive soil compaction when appropriate.

Due to use or setting, certain disturbed areas will not require compaction remediation including, but not limited to the following:

1. Within 20 feet of building foundations with basements, 12 feet from slab or crawl space construction.
2. Where soils or gravel surfaces will be required to support post-construction vehicular traffic loads such as roads, parking lots and driveways (including gravel surfaces), bicycle paths or pedestrian walkways
3. Airports
4. Areas requiring industry or government specified soil designs, including golf courses, landfills, wetland restoration, septic disposal fields, wet/land ponds, etc.
5. Areas governed or regulated by other local, state or federal regulations which dictate soil conditions
6. Brownfields (capped sues), urban redevelopment areas, , in-fill areas, , recycling yards, junk yards, quarries and
7. Slopes determined to be inappropriate for safe operation of equipment
8. Portions of a site where no heavy equipment travel or other disturbance has taken place
9. Areas receiving temporary vegetative stabilization in accordance with the Standard.
10. Where the area available for remediation practices is 500 square feet or less in size.
11. Locations containing shallow (close to the surface) bedrock conditions.

Areas of the site which are subject to compaction testing and/or mitigation shall be graphically denoted on the certified soil erosion control plan.

Soil compaction remediation or testing to prove remediation is not necessary will be required in areas where permanent vegetation is to be established that are not otherwise exempted above. Testing method shall be selected, and soil compaction testing shall be performed by, the contractor or other project owner's representative (e.g. engineer). A minimum of two (2) tests shall be performed for projects with an overall limit of disturbance of up to one (1) acre and at a rate of two (2) tests per acre of the overall limit of disturbance for larger areas which shall be evenly distributed over the area of disturbance subject to testing. Tests shall be performed in areas representative of the site's compaction potential. Where the results of the soil compaction testing indicate soil densities that exceed the maximum thresholds indicated for the testing method, the contractor/owner shall have the option to perform compaction mitigation over the entire disturbed area (excluding exempt areas) or to perform additional testing to establish the limits of excessive compaction whereupon only the excessively compacted areas would require compaction mitigation.

Soil compaction testing is not required if/when subsoil compaction remediation (scarification/tillage (6" minimum depth) or similar) is proposed as part of the sequence of construction.

Return to TOC

Soil Test Method Options

1. Probing Wire Test Method

   This test shall be conducted with a firm wire (15-1/2 gauge steel wire - e.g. survey marker flag, straight wire stock, etc.), 18 to 21 inches in length, with 6" inches from one end visibly marked on the wire. Conduct wire flag test by holding the wire flag near the flag end and push it vertically into the soil at several different locations in the field to the lesser of a 6 inch depth or the depth at which it bends due to penetration. The soil shall be considered passing if penetration fails at 6 inches. The soil shall be considered penetrable without bending or deforming at least 6" into the ground by hand, without the use of tools. If penetration fails and an obstruction is suspected (rocks, root, debris, etc.) the test can be repeated in the same general area. If the test is successful the soil is not excessively compacted. If the wire is difficult to insert (wire bends or deforms prior to reaching 6 inches in depth) the soil may be excessively compacted and compaction mitigation or further testing via method 3 or 4 below is required, the choice of which is at the contractor/owner's discretion.

2. Handheld Soil Penetrometer Test Method

   This test shall be conducted based on the Standard Operation Procedure (SOP) #SCES310-001, prepared by the Rutgers Cooperative Extension, Implemented June 1, 2010, last revised February 28, 2011. . A result of less than or equal to 300 psi shall be considered passing. If the result is greater than 300 psi the soil may be excessively compacted and compaction mitigation or further testing via method 3 or 4 below is required, the choice of which is at the contractor/owner's discretion.

3. Tube Bulk Density Test Method

   This test shall be certified by a New Jersey Licensed Professional Engineer utilizing only undisturbed samples (reconstitution of the sample not permitted) collected utilizing the procedure for Soil Bulk Density Tests as described in the USDA NRCS Soil Quality Test Kit Guide, Sections 1-4, July 2001. When the texture of the soil to be tested is a sand or loamy sand and lack of soil cohesion or the presence of large amounts of coarse fragments, roots or worm channels prevent the taking of undisturbed samples, this test shall not be used.

   Where the results of replicate tests differ by more than ten percent (10%), the samples shall be examined for the following defects:

   i. Cracks, worm channels, large root channels or poor soil tube contact within the samples;
   ii. Large pieces of gravel, roots or other foreign objects
   iii. Smearing or compaction of the upper or lower surface of the samples

   If any of the defects described in 3 (i-iii) above are found, the defective core(s) shall be discarded and the test repeated on new samples collected from the same general area of disturbance. The bulk density (defined as the weight of dry soil per volume) results shall be compared with the Maximum Dry Bulk Densities in Table 19-1. A result of less than or equal to the applicable maximum bulk density shall be considered passing. If the result is greater than the maximum bulk density the soil shall be considered excessively compacted and compaction mitigation is required.

4. Nuclear Density Test Method

   This test shall be certified by a New Jersey Licensed Professional Engineer and conducted by a nuclear gauge certified inspector pursuant to ASTM D6938. The bulk density measurement results shall be compared with the Maximum Dry Bulk Densities in Table 19-1. A result of less than or equal to the applicable maximum bulk density shall be considered passing. If the result is greater than the maximum bulk density the soil shall be considered excessively compacted and compaction mitigation is required.

Return to TOC

Table 19-1 – Maximum Dry Bulk Densities (grams/cubic centimeter) by soil type

Soil Type/Texture	Bulk Density (g/cc)
Coarse, Medium and Fine Sands and Loamy Sands	1.80
Very Fine Sand and Loamy Very Fine Sand	1.77
Sandy Loam	1.70
Coarse and Sandy Clay Loam	1.70
Clay Loams	1.65
Sandy Clay	1.60
Silt, Silt Loam	1.55
Silty Clay Loam	1.50
Silty Clay	1.45
Clay	1.40

Source: USDA Natural Resource Conservation Service, Soil Quality Information Sheet, Soil Quality Resource Concerns: Compaction, April 1996

5. Additional testing methods which conform to ASTM standards and pecifications, and which produce a dry weight, soil bulk density measurement may be allowed subject to District approval.

Procedures for Soil Compaction Mitigation

If subgrade soils are determined to be excessively compacted by testing, as identified above, procedures shall be used to mitigate excessive soil compaction prior to placement of topsoil and establishment of permanent vegetative cover. Restoration of compacted soils shall be through deep scarification/tillage (6" minimum depth) where there is no danger to underground utilities (cables, irrigation systems, etc.) or in the alternative, another method as specified by a New Jersey Licensed Professional Engineer.

Installation Requirements

Timber, logs, brush, rubbish, rocks, stumps and vegetative matter which will interfere with the grading operation or affect the planned stability or fill areas shall be removed and disposed of according to the plan.

Topsoil is to be stripped and stockpiled in amounts necessary to complete finish grading of all exposed areas requiring topsoil. See Standard for Topsoiling, pg. 8-1.

Fill material is to be free of brush, rubbish, timber, logs, vegetative matter and stumps in amounts that will be detrimental to constructing stable fills.

All structural fills shall be compacted as determined by structural engineering requirements for their intended purpose and as required to reduce slipping, erosion or excessive saturation.

All disturbed areas shall be left with a neat and finished appearance and shall be protected from erosion. See Standards for Permanent Vegetative Cover for Soil Stabilization, pg. 4-1.

Trees to be retained shall be protected if necessary in accordance with the Standard for Tree Protection During Construction, pg. 9-1.

Return to TOC

REVISION	DATE	CHKD
12		
11		
10		
9		
8		
7		
6		
5		
4 REVISED PER TOWNSHIP COMMENTS	03/31/25	SAD
3 REVISED PER ENGINEERING REVIEW	2/14/25	SAD
2 REVISED PER TOWNSHIP COMMENTS	12/19/24	SAD
1 REVISED PER PB COMPLETENESS REVIEW	09/10/24	SAD

PROJ. 08139.01-001
DWG. 08139X01
CHKD. SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREON IS THE PROPERTY OF THE WORK WAS CONTRACTED, OR IN PART, FOR ANY PURPOSE OTHER THAN MAY NOT BE COPIED, REUSED, DISCLOSED, LOANED OR ALTERED UPON OTHER PURPOSE. BOWMAN CONSULTING GROUP, LTD. ALL RIGHTS RESERVED

Bowman

Bowman Consulting Group Ltd
Suite 101, Building 3
Freehold, New Jersey 07728
Phone: 732.665.5500
FAX: 732.665.5501
E-mail: NJ@Bowman.com

N.J Certificate of Authorization No. 24GA28222600

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04437100

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL
CONSTRUCTION DETAILS- SESC
BLOCK 93, LOTS 19, 20, 45.01, 46 & 60
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

SHEET No.
17B
OF

V:\08139 – Nursery Road–Hopewell\08139-01–001 (ENG) – Venue at Hopewell SP\Engineering Plans\02- Site Plans\08139-SP–DET.dwg 03/31/25 03:52:48PM dlin.sidnell, LAYOUT:SHT–17B–SESC

MERCER COUNTY SOIL CONSERVATION DISTRICT
SOIL EROSION AND SEDIMENT CONTROL NOTES

1. The Mercer County Soil Conservation District shall be notified 48 hours prior to starting land disturbance activity, Notice may be mailed, faxed or emailed to: MCSCD, 590 Hughes Drive, Hamilton Square, NJ 08690 Phone: 609-586-9603 Fax: 609-586-1117 Email: Paul.t.mercer@aol.com
2. If applicable to this project, the owner should be aware of his or her obligation to file for a NJPDES Construction Activity Stormwater SG3 Permit (NJG0088323) via the NJDEP online permitting system (www.nj.gov/dep/online) and to maintain the associated best management practices and Stormwater Pollution Prevention Plan self-inspection logbook onsite at all times. This permit must be filed prior to the start of soil disturbance. The online application process will require entry of an SCD certification code, which is provided by the Soil Conservation District upon certification of the Soil Erosion and Sediment Control Plan.
3. The Mercer County Soil Conservation District shall be notified of any changes in ownership.
4. Any changes to the Certified Soil Erosion and Sediment Control Plan, including an increase in the limit of disturbance, will require the submission of revised Soil Erosion and Sediment Control Plans to the District for recertification. The revised plans must meet all current State Soil Erosion & Sediment Control STANDARDS.
5. A copy of the certified Soil Erosion and Sediment Control plan shall be maintained on site at all times.
6. All Soil Erosion and Sediment Control practices shall be installed prior to any major soil disturbances, or in their proper sequence as outlined within the Sequence of Construction on the Certified Soil Erosion and Sediment Control Plan, and maintained until permanent protection is established.
7. All work shall be done in accordance with the current STANDARDS for Soil Erosion and Sediment Control in NJ. If language contained within any other permit for this project is more restrictive than (but not contradictory to) what is contained within these notes or on the Certified Soil Erosion and Sediment Control Plan, then the more restrictive permit requirements shall be followed.
8. The Standard for Stabilized Construction Access requires the installation of a 1½" to 2½" clean stone tracking pad at all construction driveways immediately after initial site disturbance, whether identified on the certified plan or not. The width shall span the full width of egress, and length shall be 50 ft. or more, depending on site conditions and as required by the STANDARD. This shall include individual lot access points within residential subdivisions. If the egress is to a County road, then a 20 ft. long paved transition shall be provided between the edge of pavement and the stone access pad.
9. A sub-base course will be applied immediately following rough grading and installation of improvements in order to stabilize streets, roads, driveways and parking areas. In areas where no utilities are present, the sub-base shall be installed within 15 days of preliminary grading, provided that all other requirements related to detention basins, swales and the Sequence of Construction have been met.
10. Any disturbed areas that will be left exposed more than 14 days and not subject to construction activity will immediately receive temporary stabilization. If the season prevents establishment of a temporary vegetative cover, or if the area is not topsoiled, then the disturbed areas will be mulched with straw, or equivalent material, at a rate of two (2) tons per acre, according to State STANDARDS. Sloped areas in excess of 3H:1V shall be provided with erosion control blankets. Critical areas subject to erosion (i.e. steep slopes, roadway embankments, environmentally sensitive areas) will receive temporary stabilization immediately after an initial disturbance or rough grading.
11. Any steep slopes (i.e. slopes greater than 3:1) receiving pipeline or utility installation will be backfilled and stabilized daily, as the installation proceeds.
12. Permanent vegetation shall be seeded or sodded on all exposed areas within ten (10) days after final grading and topsoiling. All agronomic requirements contained within the STANDARDS and on the Certified Plan shall be employed. Mulch with a binder, in accordance with the STANDARDS, shall be used on all seeded areas. Save silt logs and/or bags used for seed, lime, and fertilizer, and provide them to the District inspector to verify that mixtures and rates meet the STANDARDS.
13. At the time when the site preparation for permanent vegetative stabilization is going to be accomplished, any soil that will not provide a suitable environment to support adequate vegetative ground cover shall be removed or treated in such a way that will permanently adjust the soil conditions and render it suitable for vegetative ground cover. If the removal or treatment of the soil will not provide suitable conditions, then non-vegetative means of permanent ground stabilization will have to be employed.
14. During the course of construction, soil compaction may occur within haul routes, staging areas, and other project areas. In accordance with the Standard for Topsoiling, compacted surfaces should be scarified 6" to 12" immediately prior to topsoil application. This will help ensure a good bond between the topsoil and subsoil. This practice is permissible only where there is no danger to underground utilities (cables, irrigation systems, etc.).
15. Prior to seeding, topsoil shall be worked to prepare a proper seedbed. This shall include raking of the topsoil and removal of debris and stones, along with other requirements of the Standard for Permanent Vegetative Cover for Soil Stabilization.
16. In accordance with the STANDARD for Management of High Acid Producing Soils, any soil having a pH of 4 or less or containing iron sulfides shall be buried with limestone in accordance with the STANDARD and the application of a minimum of 12" of soil having a pH of 5 or more prior to topsoil application and seedbed preparation. If the area is to receive tree or shrub plantings or is located on a slope, then the area shall be covered with a minimum of 24" of soil having a pH of 5 or more.
17. Mulching to the STANDARDS is required for obtaining a Conditional Report of Compliance. Conditional ROC's are only issued when adequate temporary stabilization is provided. Permanent stabilization must then be completed during the optimum seeding season immediately following the Conditional ROC or prior to completion of work in a given area.
18. Hydroseeding is a two-step process. The first step includes seed, fertilizer, lime, etc., along with minimal amounts of mulch to promote consistency, good seed-to-soil contact, and give a visual indication of coverage. Upon completion of the seeding operation, hydro-mulch should be applied at a minimum rate of 1500 lbs. per acre in the second step. The use of hydro-mulch, as opposed to straw, is limited to non-steep seeding dates as listed in the STANDARDS. The use of hydromulch on sloped areas is discouraged.
19. The contractor is responsible for keeping all adjacent roads clean during the life of the construction project. All sediment washed, dropped, tracked or spilled onto paved surfaces shall be immediately removed.
20. The developer shall be responsible for remediating any erosion or sediment problems that arise as a result of ongoing construction, and for employing additional erosion and sediment control measures at the request of the Mercer County Soil Conservation District.
21. Conduit Outlet Protection must be installed at all required outfalls prior to the drainage system becoming operational.
22. All detention / retention basins must be fully constructed (inclusive of all structural components and liners) and permanently stabilized prior to paving or prior to the addition of any impervious surfaces. Permanent stabilization includes, but may not be limited to: topsoil, seed, straw mulch and binders or erosion control blankets on all seeding; all agronomic requirements as specified on the Certified Soil Erosion and Sediment Control Plan, installation of the outflow control structure and discharge storm drainage piping, low flow channels, conduit outlet protection, emergency spillways, and lap ring protection.
23. The riding surface of all utility trenches within paved areas shall be 3/4" clean stone or base pavement until such time as final pavement has been installed. Temporary soil riding surfaces are prohibited. All construction dewatering (trenches, excavations, etc.) must be done through an inlet or outlet filter in accordance with the Standard for Dewatering or as depicted on the Certified Soil Erosion and Sediment Control Plan. Discharge locations for the dewatering operation must contain perennial vegetation or a similar stable surface.
24. All construction dewatering (trenches, excavations, etc.) must be done through an inlet or outlet filter in accordance with the Standard for Dewatering or as depicted on the Certified Soil Erosion and Sediment Control Plan. Discharge locations for the dewatering operation must contain perennial vegetation or a similar stable surface.
25. All swales or channels that will receive runoff from paved surfaces must be permanently stabilized prior to the installation of pavement. If the season prohibits the establishment of permanent stabilization, the swales or channels may be temporarily stabilized in accordance with the STANDARDS.
26. NJSA 4:24-39 et seq. requires that no Certificate of Occupancy or Temporary Certificate of Occupancy be issued by the Municipality before the provisions of the Certified Soil Erosion and Sediment Control Plan have been satisfied. Therefore, all site work for site plans and all work around individual lots in subdivisions must be completed before the District issues a Report of Compliance or Conditional Report of Compliance, which must be forwarded to the Municipality prior to the issuance of a Certificate of Occupancy or Temporary Certificate of Occupancy, respectively.

Mercer County Soil Conservation District
590 Hughes Dr., Hamilton Square, NJ 08690, Phone: (609) 586-9603, Fax: (609) 586-1117
Email: PaulS1Mercer@aol.com

TOPSOIL STOCKPILE PROTECTION

a) Apply ground limestone at a rate of 90 lbs/1000 S.F.
b) Apply fertilizer (10-20-10) at a rate of 11 lbs/1000 S.F.
c) Apply Perennial Rye grass seed at 1 lb/1000 S.F. and Annual Rye grass at 1lb/1000 S.F.
d) Mulch stockpile with straw or hay at a rate of 90 lbs/1000 S.F.
e) Apply a liquid mulch binder or tack to straw or hay mulch.
f) Properly entrench a silt fence at the bottom of the stockpile.

ADDITIONAL NOTES

1. Contractor shall be responsible for maintaining all permanent soil erosion and sediment control measures during construction. The property owners shall assume this responsibility after construction is completed and certificates of occupancy are issued.
2. The soil erosion inspector may require additional soil erosion measures to be installed, as directed by the district inspector.
3. The contractor is responsible for keeping the roadways clean at all times. Any sediment spilled or tracked on the roadway will be cleaned up immediately, or at minimum, by the end of each work day.

ADDITIONAL NOTES

1. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION. THE PROPERTY OWNERS SHALL ASSUME THIS RESPONSIBILITY AFTER CONSTRUCTION IS COMPLETED AND CERTIFICATES OF OCCUPANCY ARE ISSUED.
2. THE SOIL EROSION INSPECTOR MAY REQUIRE ADDITIONAL SOIL EROSION MEASURES TO BE INSTALLED, AS DIRECTED BY THE DISTRICT INSPECTOR.
3. THE CONTRACTOR IS RESPONSIBLE FOR KEEPING THE ROADWAYS CLEAN AT ALL TIMES. ANY SEDIMENT SPILLED OR TRACKED ON THE ROADWAY WILL BE CLEANED UP IMMEDIATELY, OR AT MINIMUM, BY THE END OF EACH WORK DAY.
4. ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ON INDIVIDUAL SITES SHALL APPLY TO ANY SUBSEQUENT OWNERS.
5. STEEP SLOPES TO RECEIVE A TEMPORARY SEEDING IN COMBINATION WITH STRAW MULCH OR SUITABLE EQUAL. (SEE ANCHORING NOTES & NOTE NO. 6 OF SOIL EROSION & SEDIMENT CONTROL NOTES.)
6. BERMS ALONG THE ROAD SHALL BE BROUGHT TO GRADE AND STABILIZED AS SOON AS POSSIBLE.
7. THE CONTRACTOR SHALL PROVIDE ADDITIONAL ROWS OF SEDIMENT BARRIER (SILT FENCING, HAY BALES OR STONE BERM) AS NECESSARY DURING THE COURSE OF CONSTRUCTION SUCH THAT THE CONTRIBUTION DRAINAGE AREA IS LESS THAN 1 ACRE AND THE LENGTH OF SLOPE ABOVE THE BARRIER IS LESS THAN 150'.
8. THE BASIN SHALL NOT BE UTILIZED AS A SEDIMENT BARRIER DURING CONSTRUCTION. INLET PROTECTION SHALL BE MAINTAINED DURING CONSTRUCTION AND ANY DEWTERING OPERATIONS SHALL DISCHARGE INTO SEDIMENT CONTROL BAGS.

RIPRAP SPECIFICATIONS

RIPRAP GRADATION

.HE RIPRAP SHALL BE COMPOSED OF WELL-GRADED MIXTURE SUCH THAT 50% OF THE MIXTURE BY WEIGHT SHALL BE LARGER THAN THE d50 SIZE AS DETERMINED FROM THE DESIGN PROCEDURE. A WELL-GRADED MIXTURE AS USED HEREIN IS DEFINED AS A MIXTURE COMPOSED PRIMARILY OF THE LARGER STONE SIZES BUT WITH A SUFFICIENT MIXTURE OF OTHER SIZES TO FILL THE PROGRESSIVELY SMALLER VOIDS BETWEEN THE STONES. THE DIAMETER OF THE LARGEST STONE SIZE IN SUCH A MIXTURE SHALL BE 1.5 TIMES THE d50 SIZE. THE d75 SHOULD BE 1.25 TIMES THE d50 AND THE d15 SHOULD BE 0.5 TIMES THE d50 SIZE.

THE DESIGNER AFTER DETERMINING THE RIPRAP SIZE THAT WILL BE STABLE UNDER THE FLOW CONDITION SHALL CONSIDER THAT SIZE TO BE A MINIMUM SIZE AND THEN, BASED ON RIPRAP GRADATIONS ACTUALLY AVAILABLE IN THE AREA SELECT THE SIZE OR SIZES THAT EQUAL OR EXCEED THE MINIMUM SIZE. THE POSSIBILITY OF VANDALISM SHALL BE CONSIDERED BY THE DESIGNER IN SELECTING A RIPRAP SIZE. IF THE d50 SIZE IS INCREASED, THE APRON THICKNESS SHALL BE INCREASED PROPORTIONATELY.

FILTER

SYNTHETIE FILTER FABRIC SHALL MEET THE U.S. ARMY CORPS OF ENGINEERS GUIDE SPECS, CW02215, NOVEMBER 1977 FOR STRENGTH. RIPRAP THAT IS 12" AND LARGER SHALL NOT BE DUMPED DIRECTLY ONTO SYNTHETIE FILTER CLOTH UNLESS THE MANUFACTURER RECOMMENDS SUCH USE OF THE CLOTH. OTHERWISE, A 4" MINIMUM THICKNESS BLANKET OF GRAVEL SHALL BE PLACED DIRECTLY ON THE FILTER CLOTH BY HAND OR BY THE BUCKET OF THE EQUIPMENT.

QUALITY

STONE FOR RIPRAP SHALL CONSIST OF FIELD STONE OR QUARRY STONE OF APPROXIMATELY RECTANGULAR SHAPE. THE STONE SHALL BE HARD AND ANGULAR AND OF SUCH QUALITY THAT IT WILL NOT DISINTEGRATE ON EXPOSURE TO WATER OR WEATHERING. THE SPECIFIC GRAVITY ON THE INDIVIDUAL STONES SHALL BE AT LEAST 2.5.

RUBBLE CONCRETE MAY BE USED, PROVIDED IT HAS A DENSITY OF AT LEAST 150 POUNDS PER CUBIC FOOT. AND OTHERWISE MEETS THE REQUIREMENTS OF THIS STANDARD.

STANDARD FOR
PERMANENT VEGETATIVE COVER FOR SOIL STABILIZATION

Definition

Establishment of permanent vegetative cover on exposed soils where perennial vegetation is needed for long-term protection.

Purpose

To permanently stabilize the soil, ensuring conservation of soil and water, and to enhance the environment.

Water Quality Enhancement

Slows the overland movement of stormwater runoff, increases infiltration and retains soil and nutrients on site, protecting streams or other stormwater conveyances.

Where Applicable

On exposed soils that have a potential for causing off-site environmental damage.

Methods and Materials

1. Site Preparation
   A. Grade as needed and feasible to permit the use of conventional equipment for seedbed preparation, seeding, mulch application, and mulch anchoring. All grading should be done in accordance with Standard for Land Grading.
   B. Immediately prior to seeding and topsoil application, the subsoil shall be evaluated for compaction in accordance with the Standard for Land Grading .
   C. Topsoil should be handled only when it is dry enough to work without damaging the soil structure. A uniform application to a depth of 5 inches (unsettled) is required on all sites. Topsoil shall be amended with organic matter, as needed, in accordance with the Standard for Topsoiling.
   D. Install needed erosion control practices or facilities such as diversions, grade-stabilization structures, channel stabilization measures, sediment basins, and waterways.
2. Seedbed Preparation
   A. Uniformly apply ground limestone and fertilizer to topsoil which has been spread and firmed, according to soil test recommendations such as offered by Rutgers Co-operative Extension Soil sample mailers are available from the local Rutgers Cooperative Extension offices (http://njaes.rutgers.edu/county/). Fertilizer shall be applied at the rate of 500 pounds per acre or 11 pounds per 1,000 square feet of 10-10-10 or equivalent with 50% water insoluble nitrogen unless a soil test indicates otherwise and incorporated into the surface 4 inches. If fertilizer is not incorporated, apply one-half the rate described above during seedbed preparation and repeat another one-half rate application of the same fertilizer within 3 to 5 weeks after seeding.
   B. Work lime and fertilizer into the topsoil as nearly as practical to a depth of 4 inches with a disc, spring-tooth harrow, or other suitable equipment. The final harrowing or disking operation should be on the general contour. Continue tillage until a reasonable uniform seedbed is prepared.
   C. High acid producing soil, Soils having a pH of 4 or less or containing iron sulfide shall be covered with a minimum of 12 inches of soil having a pH of 5 or more before initiating seedbed reparation. See Standard for Management of High Acid-Producing Soils for specific requirements.
3. Seeding
   A. Select a mixture from Table 4-3 or use a mixture recommended by Rutgers Cooperative Extension or Natural Resources Conservation Service which is approved by the Soil Conservation District. Seed germination shall have been tested within 12 months of the planting date. No seed shall be accepted with a germination test date more than 12 months old unless retested.

      1. Seeding rates specified are required when a report of compliance is requested prior to actual establishment of permanent vegetation. Up to 50% reduction in rates may be used when permanent vegetation is established prior to a report of compliance inspection. These rates apply to all methods of seeding. Establishing permanent vegetation means 80% vegetative coverage with the specified seed mixture for the seeded area and mowed once.

      2. Warm-season mixtures are grasses and legumes which maximize growth at high temperatures, generally 85o F and above. See Table 4-3 mixtures 1 to 7. Planting rates for warm-season grasses shall be the amount of Pure Live Seed (PLS) as determined by germination testing results.

      3. Cool-season mixtures are grasses and legumes which maximize growth at temperatures below 85oF. Many grasses become active at 65oF. See Table 4-3, mixtures 8-20. Adjustment of planting rates to compensate for the amount of PLS is not required for cool season grasses.

   B. Conventional Seeding is performed by applying seed uniformly by hand, cyclone (centrifugal) seeder, drop seeder, drill or cultipacker seeder. Except for drilled, hydroseeded or cultipacked seedings, seed shall be incorporated into the soil, to a depth of 1/4 to 1/2 inch, by raking or dragging. Depth of seed placement may be 1/4 inch deeper on coarse-textured soil.
   C. After seeding, firming the soil with a corrugated roller will assure good seed-to-soil contact, restore capillarity, and improve seeding emergence. This is the preferred method. When performed on the contour, sheet erosion will be minimized and water conservation on site will be maximized.
   D. Hydroseeding is a broadcast seeding method usually involving a truck, or trailer-mounted tank, with an agitation system and hydraulic pump for mixing seed, water and fertilizer and spraying the mix onto the prepared seedbed. Mulch shall not be included in the tank with seed. Short fibered mulch may be applied with a hydroseeder following seeding. (also see Section IV Mulching) Hydroseeding is not a preferred seeding method because seed and fertilizer are applied to the surface and not incorporated into the soil. Poor seed to soil contact occurs reducing seed germination and growth. Hydroseeding may not be used for areas too steep for conventional equipment to traverse or too obstructed with rocks, stumps, etc.
   D. Soils high in sulfides or having a pH of 4 or less refer to Standard for Management of High Acid Producing Soils, pg. 1-1.
4. Mulching

   Mulching is required on all seeding. Mulch will insure against erosion before grass is established and will promote faster and earlier establishment. The existence of vegetation sufficient to control soil erosion shall be deemed compliance with this mulching requirement.

   A. Straw or Hay. Unrotted small grain straw, hay free of seeds, applied at the rate of 1-1/2 to 2 tons per acre (70 to 90 pounds per 1,000 square feet), except that where a crimper is used instead of a liquid mulch-binder (tackifying or adhesive agent), the rate of application is 3 tons per acre. Mulch chopper-blowers must not grind the mulch. Hay mulch is not recommended for establishing the turf or lawns due to the presence of weed seed.

      Application - Spread mulch uniformly by hand or mechanically so that at least 85% of the soil surface is covered. For uniform distribution of hand-spread mulch, divide area into approximately 1,000 square feet sections and distribute 70 to 90 pounds within each section.

      Anchoring shall be accomplished immediately after placement to minimize loss by wind or water. This may be done by one of the following methods, depending upon the size of the area, steepness of slopes, and costs.

      1. Peg and Twine. Drive 8 to 10 inch wooden pegs to within 2 to 3 inches of the soil surface every 4 feet in all directions. Stakes may be driven before or after applying mulch. Secure mulch to soil surface by stretching twine between pegs in a criss-cross and a square pattern. Secure twine around each peg with two or more round turns.

      2. Mulch Nettings - Staple paper, jute, cotton, or plastic nettings to the soil surface. Use a degradable netting in areas to be mowed.

      3. Crimper (mulch anchoring coulter tool) - A tractor-drawn implement, somewhat like a disc harrow, especially designed to push or cut some of the broadcast long fiber mulch 3 to 4 inches into the soil so as to anchor it and leave part standing upright. This technique is limited to areas traversable by a tractor, which must operate on the contour of slopes. Straw mulch rate must be 3 tons per acre. No tackifying or adhesive agent is required.

      4. Liquid Mulch-Binders - May be used to anchor salt hay, hay or straw mulch.

         a. Applications should be heavier at edges where wind may catch the mulch, in valleys, and at crests of banks. The remainder of the area should be uniform in appearance.

         b. Use one of the following:

            (1) Organic and Vegetable Based Binders - Naturally occurring, powder-based, hydrophilic materials when mixed with water formulates a gel and when applied to mulch under satisfactory curing conditions will form membrained networks of insoluble polymers. The vegetable gel shall be physiologically harmless and not result in a phytotoxic effect on typical seedbed materials. Many new products are available, some of which may need further evaluation for use in this state.

            (2) Synthetic Binders - High polymer synthetic emulsion, miscible with water when diluted and, following application of mulch, drying and curing, shall no longer be soluble or dispersible in water. Binder shall be applied at rates recommended by the manufacturer and remain tacky until germination of grass.

            Note: All names given above are registered trade names. This does not constitute a recommendation of these products to the exclusion of other products.

   B. Wood-fiber or paper-fiber mulch - Shall be made from wood, plant fibers or paper containing no growth or germination inhibiting materials, used at the rate of 1,500 pounds per acre (or as recommended by the project manufacturer) and may be applied by a hydroseeder. This mulch shall not be mixed in the tank with seed. Use is limited to flatter slopes and during optimum seeding periods in spring and fall.
   C. Pelletized mulch - compressed and extruded paper and/or wood fiber product, which may contain co-polymers, tackifiers, fertilizers, and coloring agents. The dry pellets, when applied to a seeded area and watered, form a mulch mat. Pelletized mulch shall be applied in accordance with the manufacturer's recommendations. Mulch may be applied by hand or mechanical spreader at the rate of 60-75 lbs/1,000 square feet and activated with 0.2 to 0.4 inches of water. This material has been found to be beneficial for use on small lawn or renovation areas, seeded areas where weed-seed free mulch is desired, or on sites where straw mulch and tackifier agent are not practical or desirable. Applying the full 0.2 to 0.4 inches of water after spreading pelletized mulch on the seed bed is extremely important for sufficient activation and expansion of the mulch to provide soil coverage.

5. Irrigation (where feasible)

If soil moisture is deficient supply new seeding with adequate water (a minimum of 1/4 inch applied up to twice a day until vegetation is well established). This is especially true when seedings are made in abnormally dry or hot weather or on droughty sites.

6. Topdressing

Since soil organic matter content and slow release nitrogen fertilizer (water insoluble) are prescribed in Section 2A - Seedbed Preparation in this Standard, no follow-up of topdressing is mandatory. An exception may be made where gross nitrogen deficiency exists in the soil to the extent that turf failure may develop; In that instance, topdress with 10-10-10 or equivalent at 300 pounds per acre or 7 pounds per 1,000 square feet every 3 to 5 weeks until the gross nitrogen deficiency in the turf is ameliorated.

7. Establishing Permanent Vegetative Stabilization

The quality of permanent vegetation rests with the contractor. The timing of seeding, preparing the seedbed, applying nutrients, mulch and other management are essential. The seed application rates in Table 4-3 are required when a Report of Compliance is requested prior to actual establishment of permanent vegetation. Up to 50% reduction in application rates may be used when permanent vegetation is established prior to requesting a Report of Compliance from the district. These rates apply to all methods of seeding. Establishing permanent vegetation means 80% vegetative cover (of the seeded species) and mowed once. Note this designation of mowed once does not guarantee the mulch shall not be mixed in the tank with seed. Use is limited to flatter slopes and during optimum seeding periods in spring and fall.

MITIGATION NOTES FOR ACIDIC SOIL

1. LIMIT THE EXCAVATION AREA AND EXPOSURE TIME WHEN HIGH ACID PRODUCING SOILS ARE ENCOUNTERED.
2. TOPSOIL STRIPPED FROM THE SITE SHALL BE STORED SEPARATELY FROM TEMPORARILY STOCKPILED HIGH ACID PRODUCING SOILS.
3. STOCKPILES OF HIGH ACID PRODUCING SOIL SHOULD BE LOCATED ON LEVEL LAND TO MINIMIZE ITS MOVEMENT, ESPECIALLY WHEN THIS MATERIAL HAS A HIGH CLAY CONTENT.
4. TEMPORARILY STOCKPILED HIGH ACID PRODUCING SOIL MATERIAL TO BE EXPOSED MORE THAN 30 DAYS SHOULD BE COVERED WITH PROPERLY ANCHORED, HEAVY GRADE SHEETS OF POLYETHYLENE WHERE POSSIBLE. IF NOT POSSIBLE, STOCKPILES SHALL BE COVERED WITH A MINIMUM OF 3 TO 6 INCHES OF WOOD CHIPS TO MINIMIZE EROSION OF THE STOCKPILE. SILT FENCE SHALL BE INSTALLED AT THE TOE OF SLOPE TO CONTAIN MOVEMENT OF THE STOCKPILED MATERIAL. TOPSOIL SHALL NOT BE APPLIED TO THE STOCKPILES TO PREVENT TOPSOIL CONTAMINATION WITH HIGH ACID PRODUCING SOIL.
5. HIGH ACID PRODUCING SOILS WITH A pH OF 4 OR LESS, OR CONTAINING IRON SULFIDE, (INCLUDING BORROW FROM CUTS) SHALL BE ULTIMATELY PLACED OR BURIED WITH LIMESTONE APPLIED AT A RATE OF 6 TONS PER ACRE (OR 275 POUNDS PER 1,000 SQUARE FEET OF SURFACE AREA) AND COVERED WITH A MINIMUM OF 12 INCHES OF SETTLED SOIL WITH A pH OF 5 OR MORE EXCEPT AS FOLLOWS:
   A. AREAS WHERE TREES OR SHRUBS ARE TO BE PLANTED SHALL BE COVERED WITH A MINIMUM OF 24 INCHES OF SOIL WITH A pH OF 5 OR MORE.
   B. DISPOSAL AREAS SHALL NOT BE LOCATED WITHIN 24 INCHES OF ANY SURFACE OF A SLOPE OR BANK, SUCH AS BERMS, STREAM BANKS, DITCHES AND OTHERS TO PREVENT POTENTIAL LATERAL LEACHING DAMAGES.
6. EQUIPMENT USED FOR MOVEMENT OF HIGH ACID PRODUCING SOILS SHOULD BE CLEANED AT THE END OF EACH DAY TO PREVENT SPREADING OF HIGH ACID MATERIALS TO OTHER PARTS OF THE SITE, INTO STREAMS OR STORMWATER CONVEYANCES AND TO PROTECT MACHINERY FROM ACCELERATED RUSTING.
7. NON-VEGETATIVE EROSION CONTROL PRACTICES (STONE TRACKING PADS, STRATEGICALLY PLACED LIMESTONE CHECK DAM, SILT FENCE, WOOD CHIPS) SHOULD BE INSTALLED TO LIMIT THE MOVEMENT OF HIGH ACID PRODUCING SOILS FROM, AROUND OR OFF THE SITE.
8. FOLLOWING BURIAL OR REMOVAL OF HIGH ACID PRODUCING SOIL, TOPSOILING AND SEEDING OF THE SITE, (SEE TEMPORARY VEGETATIVE COVER FOR SOIL STABILIZATION, PG. 7-1, PERMANENT VEGETATIVE COVER FOR SOIL STABILIZATION, PG. 4-1 AND STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW LATEST EDITION) MONITORING SHOULD CONTINUE FOR APPROXIMATELY 6 TO 12 MONTHS TO ASSURE THERE IS ADEQUATE STABILIZATION AND THAT NO HIGH ACID SOIL PROBLEMS EMERGE. IF PROBLEMS STILL EXIST THE AFFECTED AREA MUST BE TREATED AS INDICATED ABOVE TO CORRECT THE PROBLEM.
9. MONITORING OF AREAS WHERE HIGH ACID PRODUCING SOIL HAS BEEN PLACED OR BURIED SHOULD BE PERFORMED FOR AT LEAST 2 YEARS OR LONGER IF PROBLEMS OCCUR, TO ASSURE THERE IS NO MIGRATION OF POTENTIAL ACIDE LEACHATE.

STANDARD FOR STORM SEWER INLET PROTECTION

A TEMPORARY BARRIER AND SETTLING FACILITY INSTALLED AT A STORM SEWER INLET.

DEFINITION

PURPOSE

THE PURPOSE OF STORM SEWER INLET PROTECTION IS TO INTERCEPT AND RETAIN SEDIMENT PREVENTING THE ENTRANCE OF SEDIMENT INTO THE STORM SEWER SYSTEM.

CONDITIONS WHERE PRACTICE APPLIES

1. CONTRIBUTING DRAINAGE AREA IS 3 ACRES OR LESS.
2. A STORM SEWER OR THE OUTLET CHANNEL OF A STORM SEWER NEEDS PROTECTION FROM SEDIMENT.
3. TRAFFIC WILL NOT DESTROY OR CAUSE CONSTANT MAINTENANCE OF THE STORM SEWER INLET PROTECTION.
4. A TRAFFIC HAZARD WILL NOT BE CREATED.
5. A FLOODING PROBLEM WILL NOT BE CREATED.

THE PRIMARY BENEFIT TO WATER QUALITY IS REMOVAL OF SEDIMENTS FROM STORMWATER RUNOFF. WATER QUALITY ENHANCEMENT MAY ALSO OCCUR AS AN ADDED BENEFIT, OTHER FLOATABLE DEBRIS, SUCH AS VEGETATIVE MATTER AND LITTER MAY ALSO BE FILTERED OUT OF THE RUNOFF.

THE FOLLOWING APPLIES TO ALL METHODS OF STORM SEWER INLET PROTECTION: MUST SLOW THE STORM WATER FLOW, PROVIDE THE COARSE SEDIMENT

1. PARTICLES A CHANCE TO SETTLE, AND PROVIDE AN AREA TO RETAIN THE PARTICLES THAT HAVE SETTLED. IN ALL CASES, THE INLET PROTECTION SHOULD NOT COMPLETELY
2. CLOSE OFF THE INLET, THE PROTECTION DEVICE WILL BE DESIGNED TO CAPTURE OR
3. FILTER RUNOFF FROM THE 1 YEAR, 24 HOUR STORM EVENT AND SHALL SAFELY CONVEY HIGHER FLOWS DIRECTLY INTO THE STORM SEWER SYSTEM.

OTHER METHODS THAT ACCOMPLISH THE PURPOSE OF STORM SEWER INLET PROTECTION MAY BE USED IF APPROVED BY THE SOIL CONSERVATION DISTRICT.

INSPECTIONS SHALL BE FREQUENT. MAINTENANCE, REPAIR, AND REPLACEMENT SHALL BE MADE PROMPTLY, AS NEEDED. THE BARRIER SHALL BE REMOVED WHEN THE AREA DRAINING TOWARD THE INLET HAS BEEN STABILIZED.

TEMPORARY VEGETATIVE COVER FOR SOIL STABILIZATION

Definition

Establishment of temporary vegetative cover on soils exposed for periods of two to 6 months which are not being graded, not under active construction or not scheduled for permanent seeding within 60 days.

Purpose

To temporarily stabilize the soil and reduce damage from wind and water erosion until permanent stabilization is accomplished.

Water Quality Enhancement

Provides temporary protection against the impacts of wind and rain, slows the over land movement of stormwater runoff, increases infiltration and retains soil and nutrients on site, protecting streams or other stormwater conveyances.

Where Applicable

On exposed soils that have the potential for causing off-site environmental damage.

Methods and Materials

1. Site Preparation
   A. Grade as needed and feasible to permit the use of conventional equipment for seedbed preparation, seeding, mulch application, and mulch anchoring. All grading should be done in accordance with Standards for Land Grading, pg. 19-1.
   B. Install needed erosion control practices or facilities such as diversions, grade stabilization structures, channel stabilization measures, sediment basins, and waterways. See Standards 11 through 42.
   C. Immediately prior to seeding, the surface should be scarified 6" to 12" where there has been soil compaction. This practice is permissible only where there is no danger to underground utilities (cables, irrigation systems, etc.).
2. Seedbed Preparation
   A. Apply ground limestone and fertilizer according to soil test recommendations such as offered by Rutgers Co-operative Extension. Soil sample mailers are available from the local Rutgers Cooperative Extension offices. Fertilizer shall be applied at the rate of 500 pounds per acre or 11 pounds per 1,000 square feet of 10-20-10 or equivalent with 50% water insoluble nitrogen unless a soil test indicates otherwise and incorporated into the surface 4 inches. If fertilizer is not incorporated, apply one-half the rate described above during seedbed preparation and repeat another one-half rate application of the same fertilizer within 3 to 5 weeks after seeding. Application of lime and fertilizer may be made during the period of seedbed preparation.
   B. Work lime and fertilizer into the soil as nearly as practical to a depth of 4 inches with a disc, springtooth harrow, or other suitable equipment. The final harrowing or disking operation should be on the general contour. Continue tillage until a reasonable uniform seedbed is prepared.
   C. Inspect seedbed just before seeding. If traffic has left the soil compacted, the area must be retilled in accordance with the above.
   D. Soils high in sulfides or having a pH of 4 or less refer to Standard for Management of High Acid Producing Soils, pg. 1-1.
3. Seeding
   A. Select seed from recommendations in Table 7-2.
   B. Conventional Seeding. Apply seed uniformly by hand, cyclone (centrifugal) seeder, drop seeder, drill or cultipacker seeder. Except for drilled, hydroseeded or cultipacked seedings, seed shall be incorporated into the soil, to a depth of 1/4 to 1/2 inch, by raking or dragging. Depth of seed placement may be 1/4 inch deeper on coarse textured soil.
   C. Hydroseeding is a broadcast seeding method usually involving a truck or trailer mounted tank, with an agitation system and hydraulic pump for mixing seed, water and fertilizer and spraying the mix onto the prepared seedbed. Mulch shall not be included in the tank with seed. Short fibered mulch may be applied with a hydroseeder following seeding. (also see Section IV Mulching) Hydroseeding is not a preferred seeding method because seed and fertilizer are applied to the surface and not incorporated into the soil. Poor seed to soil contact occurs reducing seed germination and growth. Hydroseeding may not be used for areas too steep for conventional equipment to traverse or too obstructed with rocks, stumps, etc.
   D. After seeding, firming the soil with a corrugated roller will assure good seed-to-soil contact, restore capillarity, and improve seedling emergence. This is the preferred method. When performed on the contour, sheet erosion will be minimized and water conservation on site will be maximized.
4. Mulching

   Mulching is required on all seeding. Mulch will insure against erosion before grass is established and will promote faster and earlier establishment. The existence of vegetation sufficient to control soil erosion shall be deemed compliance with this mulching requirement.

   A. Straw or Hay. Unrotted small grain straw, hay free of seeds, applied at the rate of 1-1/2 to 2 tons per acre (70 to 90 pounds per 1,000 square feet), except that where a crimper is used instead of a liquid mulch-binder (tackifying or adhesive agent), the rate of application is 3 tons per acre. Mulch chopper-blowers must not grind the mulch. Hay mulch is not recommended for establishing the turf or lawns due to the presence of weed seed.

      Application. Spread mulch uniformly by hand or mechanically so that approximately 95% of the soil surface will be covered. For uniform distribution of hand-spread mulch, divide area into approximately 1,000 square feet sections and distribute 70 to 90 pounds within each section.

      Anchoring shall be accomplished immediately after placement to minimize loss by wind or water. This may be done by one of the following methods, depending upon the size of the area, steepness of slopes, and costs.

      1. Peg and Twine. Drive 8 to 10 inch wooden pegs to within 2 to 3 inches of the soil surface every 4 feet in all directions. Stakes may be driven before or after applying mulch. Secure mulch to soil surface by stretching twine between pegs in a criss-cross and a square pattern. Secure twine around each peg with two or more round turns.
      2. Mulch Nettings. Staple paper, jute, cotton, or plastic nettings to the soil surface. Use a degradable netting in areas to be mowed.
      3. Crimper (mulch anchoring tool). A tractor-drawn implement, somewhat like a disc harrow, especially designed to push or cut some of the broadcast long fiber mulch 3 to 4 inches into the soil so as to anchor it and leave part standing upright. This technique is limited to areas traversable by a tractor, which must operate on the contour of slopes. Straw mulch rate must be 3 tons per acre. No tackifying or adhesive agent is required.
      4. Liquid Mulch-Binders - May be used to anchor hay or straw mulch.

         a. Applications should be heavier at edges where wind may catch the mulch, in valleys, and at crests of banks. The remainder of the area should be uniform in appearance.

         b. Use one of the following:

            (1) Organic and Vegetable Based Binders - Naturally occurring, powder based, hydrophilic materials when mixed with water formulates a gel and when applied to mulch under satisfactory curing conditions will form membrained networks of insoluble polymers. The vegetable gel shall be physiologically harmless and not result in a phytotoxic effect on typical seedbed materials. Many new products are available, some of which may need further evaluation for use in this state.

            (2) Synthetic Binders - High polymer synthetic emulsion, miscible with water when diluted and following application to mulch, drying and curing shall no longer be soluble or dispersible in water. It shall be applied at rates recomm

Slopes Table - Proposed Disturbance				
Number	Minimum Slope	Maximum Slope	S.F.	Allowed
1	0.0%	15.0%	5,433,272	100% (7,567,980 SF)
2	15.0%	25.0%	54,866	15% (28,264 SF)
3	25.0%	1000.0%	4,260	0% (0 SF)

= LIMIT OF DISTURBANCE

Slopes Table - Total within Property Line				
Number	Minimum Slope	Maximum Slope	S.F.	Color
1	0.00%	15.00%	7,568,144	
2	15.00%	25.00%	188,169	
3	25.00%	100.00%	14,290	



REVISION	DATE	CHKD
12		
11		
10		
9		
8		
7		

REVISION	DATE	CHKD
6		
5	03/31/25	SAD
REVISED PER TOWNSHIP COMMENTS		
4	2/14/25	SAD
REVISED PER ENGINEERING REVIEW		
3	12/18/24	SAD
REVISED PER TOWNSHIP COMMENTS		
2	09/10/24	SAD
REVISED PER PB COMPLETENESS REVIEW		
1		

PROJ. 08139-01-001
DATE: 9/6/2024
CHKD: SAD

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE PROPERTY OF THE WORK WAS CONTRACTED FOR THE SPECIFIC PROJECT LISTED HEREON AND MAY NOT BE COPIED, REUSED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE EXPRESS WRITTEN CONSENT OF BOWMAN CONSULTING GROUP LTD.
© BOWMAN CONSULTING GROUP LTD.
ALL RIGHTS RESERVED

Bowman

Bowman Consulting Group Ltd
Woodmont Corporate Center
Freehold, New Jersey 07728
Phone: 732-665-5500
FAX: 732-665-5501
E-mail: NJ@bowman.com

Phone: 732-665-5500
FAX: 732-665-5501
NJ Certificate of Authorization
No. 24GA0922900

SEAN A. DELANY, N.J. Professional Engineer, Lic. 24GE04467100

PRELIMINARY AND FINAL MAJOR SUBDIVISION &
PRELIMINARY AND FINAL SITE PLAN FOR
VENUE AT HOPEWELL

STEEP SLOPES PLAN

BLOCK 93, LOTS 19, 20, 45.01, 46 & 60
TOWNSHIP OF HOPEWELL, MERCER COUNTY, NEW JERSEY

SHEET No.
25
OF

N:\08139 – Nursery Road–Hopwell\08139-01-001 (ENG) – Venue at Hopewell SP\Engineering\Engineering Plans\02_Site Plans\08139-SP-SteepSlopePlan.dwg 03/31/25 03:47:41PM, dino.spinelli, LAYOUT:STEEP SLOPES